



**REGIONAL OFFICE (MAHARASHTRA)
EMPLOYEES' STATE INSURANCE CORPORATION
(Ministry of Labour & Employment, Government of India)
Regional Office, Panchdeep Bhavan, N.M Joshi Marg,
Lower Parel, Mumbai-400013**

Phone: 02261209775/97

Web Site: www.esic.nic.in

<https://eprocure.gov.in/eprocure/app>, e-mail:- support-eproc@nic.in

e-mail id: construction-mh@esic.nic.in

**e - TENDER
FOR**

**“ANNUAL REPAIR & MAINTENANCE OF CIVIL WORKS OF DISPENSARY CUM
BRANCH OFFICE INCLUDING STAFF QUARTERS AT WALUJ, AURANGABAD”**

BID DOCUMENT

Issued by

(Regional Director)

INDEX

Sl. No	Subject	Annexure	Page No.
1	Notice Inviting e-Tender	A	3-4
2	Important Instructions to the Bidders regarding online payment	B	5-7
3	Eligibility Criteria for Bidders	C	8
4	Instructions to bidders	D	9-13
5	Scope of work	E	14
6	General conditions of contract	F	15-21
7	Particular conditions of contract	G	22-23
8	Additional Terms & Conditions For Civil Works	P	24-25
9	List of Preferred Make		26-29
10	Testing of Material		30
11	Contract Agreement	H	31-32
12	Form of Performance Security / Bank Guarantee Bond	I	33-34
13	Technical Bid Performa	J	35- 36
14	Experience of Company	K	37
15	Undertaking	L	38
16	Consent letter from eligible associate agency of minor Component of work	M	39
17	Memorandum of Understanding (M.O.U) (to be submitted for each and every Minor component)	N	40-41
18	Guarantee Bond for Water proofing work	O	42
19	Bill of Quantities (Financial Bid)	Q	43-67



**REGIONAL OFFICE (MAHARASHTRA)
EMPLOYEES' STATE INSURANCE CORPORATION
(Ministry of Labour & Employment, Government of India)
Regional Office, Panchdeep Bhavan, N.M Joshi Marg,
Lower Parel, Mumbai-400013**

Phone: 022 61209797 /75

Web Site: www.esic.nic.in

<https://eprocure.gov.in/eprocure/app>, e-mail:- support-eproc@nic.in

e-mail id: construction-mh@esic.nic.in

Notice Inviting e-Tender

“ANNUAL REPAIR & MAINTENANCE OF CIVIL WORKS OF DISPENSARY CUM BRANCH OFFICE INCLUDING STAFF QUARTERS AT WALUJ, AURANGABAD”

Online **Percentage Rate Tender** under two stage system are invited from eligible contractors registered eligible to tender for works up to amount permitted by virtue of his enlistment limit with C.P.W.Ds /State P.W.Ds./M.E.S./Railways/BSNL Civil and Electrical wing or any other government body as Civil Contractor for **ANNUAL REPAIR & MAINTENANCE OF CIVIL WORKS OF DISPENSARY CUM BRANCH OFFICE INCLUDING STAFF QUARTERS AT WALUJ, AURANGABAD.**

Sl.	Item	Detail
1	Name of work	ANNUAL REPAIR & MAINTENANCE OF CIVIL WORKS OF DISPENSARY CUM BRANCH OFFICE INCLUDING STAFF QUARTERS AT WALUJ, AURANGABAD.
2	Time for Completion	12 Months
3	Estimated Cost	Rs. 37,04,399/- (Rupees Thirty-Seven Lacs Four Thousand Three Hundred Ninety-Nine Only)
4	Earnest Money Deposit (EMD)	The amount of Earnest Money Deposit (EMD) of Rs. 74,088/- which shall be in the form of deposit at call receipt of a Scheduled Bank/ Fixed Deposit receipt of Scheduled Bank/Demand Draft of scheduled Bank issued / drawn in favour of 'ESI FUND ACCOUNT No.1', payable at Mumbai on or before 04.09.2019 till 04:00 PM.

5	Tender Document	The tender document may be downloaded from www.esic.nic.in/tenders , and https://eprocure.gov.in/eprocure/app from 06.08.2019 at 11:00 AM to 04.09.2019 till 04:00 PM.
6	Last Date of submission	Technical bid and finance bid must be submitted online at https://eprocure.gov.in/eprocure/app during period from 06.08.2019 at 11:00 AM to 04.09.2019 till 04:00 PM. Bid submitted through any other mode shall not be entertained.
7	Date of opening of tender:	The technical bids of tenders shall be opened in the presence of the tenderers who desire to be present on 05.09.2019 till 04:00 PM at 2nd Floor, RO Lower Parel, Mumbai. In case 05.09.2019 is declared a public holiday, tenders shall be opened as per above schedule on next working day. The date for opening of Financial Bid of those bids who are found Technically qualified shall be Communicated separately.

Regional Director
Employees' State Insurance Corporation

Instructions for Online Bid Submission

(Department User may attach this Document as an Annexure in their Tender Document which provides complete Instructions for on line Bid submission for Bidders)

The bidders are required to submit soft copies of their bids electronically on the CPP Portal, using valid Digital Signature Certificates. The instructions given below are meant to assist the bidders in registering on the CPP Portal, prepare their bids in accordance with the requirements and submitting their bids online on the CPP Portal.

More information useful for submitting online bids on the CPP Portal may be obtained at: <https://eprocure.gov.in/eprocure/app>.

REGISTRATION

- 1) Bidders are required to enrol on the e-Procurement module of the Central Public Procurement Portal (URL: <https://eprocure.gov.in/eprocure/app>) by clicking on the link “**Online bidder Enrolment**” on the CPP Portal which is free of charge.
- 2) As part of the enrolment process, the bidders will be required to choose a unique username and assign a password for their accounts.
- 3) Bidders are advised to register their valid email address and mobile numbers as part of the registration process. These would be used for any communication from the CPP Portal.
- 4) Upon enrolment, the bidders will be required to register their valid Digital Signature Certificate (Class III Certificates with signing key usage) issued by any Certifying Authority recognized by CCA India (e.g. Sify / nCode / eMudhra etc.), with their profile.
- 5) Only one valid DSC should be registered by a bidder. Please note that the bidders are responsible to ensure that they do not lend their DSC’s to others which may lead to misuse.
- 6) Bidder then logs in to the site through the secured log-in by entering their user ID / password and the password of the DSC / e-Token.

SEARCHING FOR TENDER DOCUMENTS

- 1) There are various search options built in the CPP Portal, to facilitate bidders to search active tenders by several parameters. These parameters could include Tender ID, Organization Name, Location, Date, Value, etc. There is also an option of advanced search for tenders, wherein the bidders may combine a number of search parameters such as Organization Name, Form of Contract, Location, Date, Other keywords etc. to search for a tender published on the CPP Portal.
- 2) Once the bidders have selected the tenders they are interested in, they may download the required documents / tender schedules. These tenders can be moved to the respective ‘My Tenders’ folder. This would enable the CPP Portal to intimate the bidders through SMS / e-mail in case there is any corrigendum issued to the tender document.
- 3) The bidder should make a note of the unique Tender ID assigned to each tender, in case they want to obtain any clarification / help from the Helpdesk.

PREPARATION OF BIDS

- 1) Bidder should take into account any corrigendum published on the tender document before submitting their bids.
- 2) Please go through the tender advertisement and the tender document carefully to understand the documents required to be submitted as part of the bid. Please note the number of covers in which the bid documents have to be submitted, the number of documents - including the names and content of each of the document that need to be submitted. Any deviations from these may lead to rejection of the bid.
- 3) Bidder, in advance, should get ready the bid documents to be submitted as indicated in the tender document / schedule and generally, they can be in PDF / XLS / RAR / DWF/JPG formats. Bid documents may be scanned with 100 dpi with black and white option which helps in reducing size of the scanned document.
- 4) To avoid the time and effort required in uploading the same set of standard documents which are required to be submitted as a part of every bid, a provision of uploading such standard documents (e.g. PAN card copy, annual reports, auditor certificates etc.) has been provided to the bidders. Bidders can use “My Space” or “Other Important Documents” area available to them to upload such documents. These documents may be directly submitted from the “My Space” area while submitting a bid and need not be uploaded again and again. This will lead to a reduction in the time required for bid submission process.

Note: *My Documents space is only a repository given to the Bidders to ease the uploading process. If Bidder has uploaded his Documents in My Documents space, this does not automatically ensure these Documents being part of Technical Bid.*

SUBMISSION OF BIDS

- 1) Bidder should log into the site well in advance for bid submission so that they can upload the bid in time i.e. on or before the bid submission time. Bidder will be responsible for any delay due to other issues.
- 2) The bidder has to digitally sign and upload the required bid documents one by one as indicated in the tender document.
- 3) Bidder has to select the payment option as “offline” to pay the tender fee / EMD as applicable and enter details of the instrument.
- 4) Bidder should prepare the EMD as per the instructions specified in the tender document. The original should be posted/couriered/given in person to the concerned official, latest by the last date of bid submission or as specified in the tender documents. The details of the DD/any other accepted instrument, physically sent, should tally with the details available in the scanned copy and the data entered during bid submission time. Otherwise the uploaded bid will be rejected.
- 5) Bidders are requested to note that they should necessarily submit their financial bids in the format provided and no other format is acceptable. If the price bid has been given as a standard BoQ format with the tender document, then the same is to be downloaded and to be filled by all the bidders. Bidders are required to download the BoQ file, open it and complete the white coloured (unprotected) cells with their respective financial quotes and other details (such as name of the bidder). No other cells should be changed. Once the details have been completed, the bidder should save it and submit it online, without changing the filename. If the BoQ file is found to be modified by the bidder, the bid will be rejected.

6) The server time (which is displayed on the bidders' dashboard) will be considered as the standard time for referencing the deadlines for submission of the bids by the bidders, opening of bids etc. The bidders should follow this time during bid submission.

7) All the documents being submitted by the bidders would be encrypted using PKI encryption techniques to ensure the secrecy of the data. The data entered cannot be viewed by unauthorized persons until the time of bid opening. The confidentiality of the bids is maintained using the secured Socket Layer 128 bit encryption technology. Data storage encryption of sensitive fields is done. Any bid document that is uploaded to the server is subjected to symmetric encryption using a system generated symmetric key. Further this key is subjected to asymmetric encryption using buyers/bid opener's public keys. Overall, the uploaded tender documents become readable only after the tender opening by the authorized bid openers.

7) The uploaded tender documents become readable only after the tender opening by the authorized bid openers.

8) Upon the successful and timely submission of bids (i.e. after Clicking "Freeze Bid Submission" in the portal), the portal will give a successful bid submission message & a bid summary will be displayed with the bid no. and the date & time of submission of the bid with all other relevant details.

9) The bid summary has to be printed and kept as an acknowledgement of the submission of the bid. This acknowledgement may be used as an entry pass for any bid opening meetings.

ASSISTANCE TO BIDDERS

1) Any queries relating to the tender document and the terms and conditions contained therein should be addressed to the Tender Inviting Authority for a tender or the relevant contact person indicated in the tender.

2) Any queries relating to the process of online bid submission or queries relating to CPP Portal in general may be directed to the 24x7 CPP Portal Helpdesk.

ELIGIBILITY CRITERIA FOR BIDDERS

S N	COMPONENT OF WORK	ESTIMATED COST (Rs.)	ELIGIBILITY
1.	ANNUAL REPAIR & MAINTNANCE OF CIVIL Works (Major Component)	Rs. 37,04,399/-	Registered contractors of C.P.W.Ds /State P.W.Ds./M.E.S./ Railways / BSNL Civil wing or any other government body as Civil Contractor eligible to tender for works up to amount permitted by virtue of his enlistment limit.

Rest Eligibility conditions as given below.

1. The bidder should have minimum three years' experience as on Last day of the month previous to the one in which tenders are invited in similar nature of works. (Similar nature of works means that the applicant should have completed the Annual Repair and Maintenance in Civil works or the minor structural repair, water supply, sanitary / plumbing, installation, drainage works, repair of road work & similar external services in Central Govt. offices/ State Govt. Offices / attached offices / statutory bodies / PSU departments).
2. Average Annual Financial turnover during the immediate last 3 consecutive financial years should be at least 30% of the value of work to be executed (copies of balance sheets signed by Chartered Accountant to be submitted online).
3. The applicant should have also successfully completed similar works in Central Govt. offices / State Govt. offices / attached offices / statutory bodies / PSU departments during the period of last seven years ending on Last day of the month previous to the one in which tenders are invited either of the following:
 - a) Three similar completed works costing not less than the amount equal to 40% of estimated cost put to tender i.e. **Rs. 14,81,760/- (each)**.
or
 - b) Two similar completed works costing not less than the amount equal to 60% of estimated cost put to tender i.e. **Rs. 22,22,639/- (each)**.
or
 - c) One similar completed works costing not less than the amount equal to 80% of estimated cost put to tender i.e. **Rs. 29,63,519/- (each)**.(Their completion certificate along with cost of the work, period and nature of work in the prescribed Performa of the concerned department duly signed by the competent authority should be furnished Online)
4. The Tenderer must have been registered in C.P.W.Ds/State P.W.Ds. /M.E.S./ Railways/BSNL Civil Wing or any other government body as Civil Contractor eligible to tender for works up to amount permitted by virtue of his enlistment limit.
5. The tenderers must have to submit a Self-certificate that they have not been indicated for any criminal, fraudulent or anti-competition activity and has not been blacklisted by any Govt. departments or otherwise.
6. All documents as stated in point no. 2.2 of Annexure – D must be submitted online in Technical Bid.

INSTRUCTIONS TO THE BIDDERS

1. Earnest Money Deposit:

- 1.1. The Earnest Money of **Rs. 74,088/-** in the form of Fixed Deposit receipt of Scheduled Bank/Demand Draft of scheduled Bank issued / drawn in favour of '**ESI FUND ACCOUNT No.1**', payable at Mumbai shall be dropped on or before **04.09.2019 till 04:00 PM** in the tender box placed at Construction Branch, ESI Corporation, Regional Office, Lower Parel, Mumbai. The bid received without submission of EMD will summarily be rejected.
- 1.2. EMD shall be placed in separate sealed cover by writing the **ANNUAL REPAIR & MAINTENANCE OF CIVIL WORKS OF DISPENSARY CUM BRANCH OFFICE INCLUDING STAFF QUARTERS AT WALUJ, AURANGABAD** on the envelope. If the Earnest Money is not found as per the prescribed manner, then Technical/Financial Bid shall not be opened.
- 1.3. EMD as above mentioned will be accepted in above manner shall accompany the bid.
- 1.4. EMD shall remain valid for a period of 90 days. A bid received without Bid Security (EMD) shall be rejected at the bid opening stage.
- 1.5. The earnest money shall be refunded to the unsuccessful tenderers after finalization of the contract.
- 1.6. No interest is payable on the EMD/SD.
- 1.7. The bid security (EMD) may be forfeited, if a bidder withdraws his bid during the specified period of bid validity, specified in the bid documents. In the case of successful bidder, if the bidder fails to submit the agreement bond along with Performance Guarantee within time specified in the Tender document after awarding of the contract, ESIC shall without prejudice to any other right or remedy available in Law, be at liberty to forfeit the earnest money absolutely.
- 1.8. Letter of authorization to attend bid opening.

2. Submission of bids: -

- 2.1. Each and every page of the tender documents should bear the stamp and signature of the person whose name registration exists or he/she shall be authorized legally or any representative by clearly mentioning the name and stating that the person can sign the tender documents on his behalf. Format enclosed shall be filled without exception, specially Annexure 'L' of Undertaking.
- 2.2. The tenderer should take care to upload online all the information sought by the Employees State Insurance Corporation in prescribed formats. Also, the tenderer has to upload online the scan copy of following documents along with the technical bid: -
 - (a) **E.M.D. of Rs. 74,088/-**
 - (b) PAN Card
 - (c) Clause by clause compliance demonstrating substantive responsiveness to the commercial condition by signing and stamping on all the pages of the original bid documents in online submission.

- (d) Certificate of Incorporation/ Shop & Establishment Registration Certificate of Firm/ Memorandum and Article of Association/ Partnership Deed/ Proprietorship Deed/ Declaration of proprietorship etc. as the case may be.
- (e) Balance sheet/ P & L Account of the firm for last three financial years (**i.e. for the year 2015-16, 2016-17 & 2017-18**).
- (f) Income Tax Return of the Firm for last three financial years (**i.e. for the year 2015-16, 2016-17 & 2017-18**).
- (g) GST Registration Certificate.
- (h) Annual turnover of works for immediate last 3 consecutive financial years **i.e. for the year 2015-16, 2016-17 & 2017-18, duly** certified by Chartered Accountant.
- (i) Satisfactory completion certificate of similar nature of work (as per sr. no. 3 of Annexure –C, i.e. eligibility condition)
- (j) Registration Certificate of the firm under ESIC.
- (k) Registration Certificate of the firm under EPFO.
- (l) Valid License/ Registration of the firm from C.P.W.Ds/ State P.W.Ds./M.E.S./Railways/BSNL Civil wing or any other government body as Civil contractor.
- (m) Registration certificate of the firm under the Contract Labour (Regulation & Abolition) Act 1970 & Contract Labour Central Rule (Regulation & Abolition) 1971 or undertaking for obtaining Labour Licence if qualified in financial Bid.
- (n) Professional Tax Registration Certificate.
- (o) A self-certificate that they have not been indicted for any criminal, fraudulent or anti-competition activity and has not been blacklisted by any Govt. departments or otherwise.
- (p) Complete Bank Details/ Cancelled Cheque

Technical bid shall be opened on the date as mentioned in NIT. The financial bid of the tender shall be opened only for the tenders, which qualify in the technical bid. The date for opening of Financial Bid will be Communicated Separately.

2.3 **Financial Bid:**

Financial bid must be submitted online only at <https://eprocure.gov.in/eprocure/app>. The financial bid of the tenderers, whose technical bid is found to be qualified, will be opened in the presence of the tenderers, who desire to attend the opening of financial bid.

3. EMD (as per Annexure-‘D’-1.1) may be dropped in the tender box on or before **04.09.2019 till 04:00 PM** placed at following address :

**Construction Branch
Regional Office
Employees State Insurance Corporation
Panchdeep Bhavan-108, N.M. Joshi Marg,
Lower Parel, Mumbai-400013**

4. The site for the work can be seen on any working days during office hours by contacting 'Branch Officer, Construction Branch, Employees' State Insurance Corporation, Panchdeep Bhavan-108, N.M. Joshi Marg, Lower Parel, Mumbai-13'. The tenderers are advised to inspect and examine the site and its surroundings and satisfy themselves before submitting the tenders, the form and nature of site, the means of access to the site etc. A tenderer shall be deemed to have full knowledge of the site whether he inspects it or not and no extra charges consequent on any misunderstanding or otherwise shall be allowed.
5. Canvassing whether directly or indirectly, in connection with tenders strictly prohibited and the tenders submitted by the contractors who resort to canvassing will be liable to rejection.
6. The work shall remain open for acceptance for a period of **90** days from the date of opening of tenders. If any tenderer withdraws his tender before the said period or issue of letter of acceptance/Indent whichever is earlier or makes any modifications in the terms and conditions of the tender which are not acceptable by the ESIC and, shall be without prejudice to any other right or remedy, be at liberty to forfeit 50% of the said earnest money.
7. **Rights of Acceptance/ Rejection:**
Regional Director, ESI Corporation, Maharashtra reserves the right to reject all or any tender in whole, or in part, without assigning any reason thereof. The competent authority on behalf of ESIC does not bind himself to accept the lowest or any other tender and reserves the right to reject any or all of the tenders without assigning any reasons thereof. All the tenders, in which any of the prescribed conditions is not fulfilled or any condition including that of conditional rebate is put forth by the tenderer, shall be summarily rejected.
8. **PERFORMANCE GUARANTEE:**
 - 8.1 The successful contractor will be required to furnish an irrevocable PERFORMANCE GUARANTEE of 5% (Five percent) of the tendered amount in addition to other deposit mentioned elsewhere in the contract for his proper performance of the contract (not withstanding and /or without prejudice to any other provisions in the contract) within 10 days from the date of issue of letter of acceptance of tender.
 - 8.2 The guarantee shall be in the form of Demand Draft/ Banker's Cheque or of Fixed Deposit Receipts pledged to 'ESI Fund A/c No. 1' or Irrevocable bank Guarantee Bonds of any scheduled Bank or the State Bank of India in the format as per Annexure-'I'. In case, a fixed deposit receipt of any bank is furnished by the contractor to ESIC as a part of performance guarantee and the bank is unable to make payment against the said fixed deposit receipt, the loss caused thereby shall fall on the contractor and the contractor shall forthwith on demand furnish additional security to ESIC to make good the deficit.

- 8.3 The Performance Guarantee shall be initially valid for a period up to **365** days beyond the Stipulated Contract Period. In case the Contract Period of work gets extended, the contractor shall get the validity of Performance Guarantee extended, at his own cost; to cover such extended time for Contract Period.
- 8.4 EMD shall be returned to the successful bidder after receiving Performance Guarantee from he/she/them and making Contract Agreement with him/her/them.
9. Letter of Acceptance of tender/Work Order shall be issued in the first instance to the successful tenderer with the decision/approval of the competent authority and letter for commencement of work awarded shall be issued only after the Performance Guarantee in the prescribed form is received from the successful tenderer/contractor. In case of failure of the contractor to furnish the Performance Guarantee within the specified period, the ESIC shall without prejudice to any other right or remedy available in Law, be at liberty to forfeit the earnest money absolutely.
10. **SECURITY DEPOSIT:** The contractor shall permit ESIC at the time of making any payment to him for work done under the contract to deduct a sum at the rate of 2.5% of the gross amount of each running bill value of the work. Such deductions will be made and held by ESIC by way of Security Deposit. Security Deposit would be released after satisfactory completion of defect liability period.
11. On acceptance of the tender, the name of the accredited representative(s) of the contractor, who would be responsible for taking instructions from the Engineer/Authority, shall be communicated in writing to the ESIC.
12. Central Sales Tax, Local Sales Tax, VAT, Purchase Tax, Turn over Tax, Service Tax, GST or any other tax, wherever applicable, inclusive of all cess and all duties in respect of the contract, must be payable by the contractor. The ESIC will not entertain any claim what so ever in respect of the same.
13. Rates quoted by Contractor/Tenderer shall be deemed to have inclusive of cost of manpower, material, machinery, tools, plants, Contractor's Overhead and Profit etc. & all taxes including GST, duties, levies, Cess, ESI, EPF, Insurance etc. No escalation of whatsoever nature shall be payable.
14. The tenderers shall produce their valid enlistment with the appropriate authority for all types of Taxes, GST, Cess, Duty, contribution etc.
15. Rates quoted by the Contractor/Tenderer shall also be inclusive of 1% (one percent) Cess on the work done as applicable on the Building & Other Construction Workers' Welfare Cess Act 1996 due to the introduction of "The Building & Other Construction Workers (Regulation of Employment & Conditions of Services) Act 1996".
16. **Award of work:**
- i The selection of the agency will be at the sole discretion of the Employees State Insurance Corporation, who reserves the right to accept one or to reject any or all the tenders without assigning any reasons thereof.
 - ii The contract shall be awarded to the best qualified responsive tender.
 - iii Upon evaluation of offers, the written notification for award of contract will be intimated to the successful tenderer to start the work.

Regional Director,
Employees' State Insurance Corporation

Sign & Seal of the Contractor:

Date:

Place:

SCOPE OF WORK

Details of Premises/buildings:

Sr. No.	Name and Address of Building	Nature of Facility
1	ANNUAL REPAIR & MAINTENANCE OF CIVIL WORKS OF DISPENSARY CUM BRANCH OFFICE INCLUDING STAFF QUARTERS AT WALUJ, AURANGABAD.	REPAIR AND MAINTENANCE

Scope of Works/Services:

1. Day to day maintenance though Annual Repair & Maintenance as per Work Schedule & Techno-functional requirement of works at site.
2. Any other works as and when directed by the authorized person from ESIC other than mentioned above falling under the domain of Civil works.

GENERAL CONDITIONS OF CONTRACT

1 Definitions

In the Contract (as hereinafter defined) the following words and expressions shall have the meanings hereby assigned to them except where the context otherwise requires:

- (i) **“Employer”** means the Employees' State Insurance Corporation and the legal successors in title to Employees' State Insurance Corporation.
- (ii) **“Engineer”** means the person appointed by Employees' State Insurance Corporation to act as an Engineer for the purpose of the Contract.
- (iii) **“Contractor”** means an individual or firms whether incorporated or not, that has entered into contract (with the employer) and shall include his/its heirs, legal representatives, successors and assignees. Changes in the constitution of the firm, if any, shall be immediately brought to the notice of the employer, in writing and approval shall be obtained for continue performance of the contract.
- (iv) **“Contract”** means the conditions, the Specifications, the Bill of Quantities, the Tender, the Letter of acceptance, the Contract Agreement (if completed) and such other documents as may be expressly incorporated in the Letter of Acceptance or Contract Agreement. (As per Annexure ‘H’)
- (v) **“Specification”** means the specification of the works included in the contract and any modification thereof. The items of works shall be executed in strict accordance of CPWD specifications.
- (vi) **“Drawings”** means all the completion drawings, calculations and technical information of a like nature provided by the Engineer to the Contractor under this contract and all drawings, calculations, samples, patterns, models, Repair/Repairs and Maintenance manuals and other technical information of a like nature submitted by the Contractor and approved by the Engineer.
- (vii) **“Bill of Quantities”** means the priced and completed bill of quantities forming part of the Tender.
- (viii) **“Tender”** means the Contractor's priced offer to the Employer for the execution and satisfactory completion of the works and the remedying of any defects therein in accordance with the provisions of the Contract, Specification as accepted by the Letter of Acceptance. The word Tender is synonymous with “Bid” and the words “Tender Documents” with “Bidding Documents”.
- (ix) **“Letter of Acceptance”** means the formal acceptance of the tender by Employees' State Insurance Corporation in writing.
- (x) **“Contract Agreement”** means the contract agreement (if any) referred to contract agreement as per Annexure ‘H’.
- (xi) **“Appendix to Tender”** means the appendix comprised in the form of Tender annexed to these Conditions.
- (xii) **“Commencement Date”** means the date from which the Contractor is directed by ESIC to start the works in writing.
- (xiii) **“Time for Completion”** means the time period for which the contract has been allowed to be completed by the employer to the contractor.
- (xiv) **“Taking Over Certificate”** means a certificate issued by employer evidencing successful and satisfactory completion of the awarded work as per contract agreement.
- (xv) **“Contract Price”** means the sum stated in the Letter of Acceptance as payable to the Contractor for the execution and completion of the Works and removing of any defects therein in accordance with the provisions of the Contract.
- (xvi) **“Extra Item Price”** Any items of works if it is not available in Bill of Quantities and

required to be executed in the interest of completion of work.

- (xvii) **“Substitute Item Price”** Any items of works required to be executed in the interest of completion of work and replace by the similar item available in Bill of Quantities.
- (xviii) **“Retention Money”** means the aggregate of amount retained by the Employer as Security Deposit.
- (xix) **“Works”** means the Permanent Works and the Temporary Works or either of them to be executed in accordance under the contract and contract specifications.
- (xx) **“Site”** means the places provided by the Employer to the Contractor.
- (xxi) **“Cost”** means all expenditure properly incurred or to be incurred, whether on or off the Site, including overhead and other charges but does not include any allowance for profit.

2. Engineer’s Duties and Authority

The Engineer shall carry out the duties as specified in the Contract.

3. Custody and Supply of Drawings and Documents

The Drawings shall remain in the sole custody of the Employer but copies as required thereof shall be provided to the Contractor for free solely for the purpose of this contract.

4. Sufficiency of Tender

The Contractor shall be deemed to have based his Tender on the data made available by the Employer and on his own inspection and examination of this site conditions. The acceptance of tender is deemed to have visited the site and made themselves conversant with the type of works incorporated in this tender.

5. Contractor's Employees

The Contractor shall provide qualified and experienced technical staff on the site of work in connection with the works and for remedy of any defects therein.

6. Engineer at Liberty to Object

The Engineer shall be at liberty to object, to remove forthwith from the Works, any person provided by the Contractor who, in the opinion of the Engineer, misconducts himself, or is incompetent or negligent in the proper performance of his duties, or whose presence on site is otherwise considered by the Engineer to be undesirable and such person shall not be again allowed upon the Works without the consent of the Engineer. Any person so removed from the Works shall be replaced immediately.

7. Safety, Security and Protection of the Environment

The Contractor shall, throughout the execution and till completion of the Works remedying of any defects therein:

- (i) Have full regard for the safety of all persons entitled to be upon the site and keep the site (so far as the same is under his control) and the Works (so far as the same are not completed or occupied by the Employer) in an orderly state appropriate to the avoidance of danger to such persons, and

(ii) Provide and maintain at his own cost all lights, guards, fencing, warning signs and watching, when and where necessary or required by the Engineer or by any duly constituted authority for the protection of the Works or for the safety and convenience of the public or others, and

(iii) Take all reasonable steps to protect the environment on and off the Site and to avoid damage or nuisance to persons or to property of the public or others, resulting from pollution, noise or other causes arising as a consequence of his methods of doing work activities under the contract.

(iv) All safety rules prescribed by the Government should be complied and shall be strictly observed to execute the work and safety of manpower deployed.

8. (A) Insurance of work by the Contractor for his liability:

(i) During the execution of the work any loss or damage to the property and life of his employee arising from a cause for which contractor is responsible.

(ii) For loss or damage occasioned by the Contractor in the course of any work carried out by him for the purpose of complying with his obligations.

(iii) It shall be the responsibility of contractor to notify the Insurance Company of any change in the nature and extent of the works and to ensure the adequacy of the Insurance cover at all times during the period of contract.

(B) Damage to Persons and Property

The Contractor shall, except if and so far as the Contract provides otherwise, indemnify the Employer against all losses and claims in respect of :

(a) Death or injury to any person, or

(b) Loss or damage to any property (other than the Works):

Which may arise out of or in consequence of the Annual Repair & Maintenance of the works and the remedying of any defects therein, and against all claims, proceedings, damages, costs, charges and expenses whatsoever in respect thereof.

9. Accident or injury to Workmen

The Employer shall not be liable for or in respect of any damages or compensation payable to any workman under Compensation Act for death or injury resulting from any act or default of the contractor. The contractor shall indemnify and keep indemnified the Employer against all such damages and compensation and expenses whatsoever in respect thereof or in relation thereto.

10.1 Evidence and Terms of Insurance

The contractor shall take out appropriate insurance to cover his work, workers and staff employed by him fully. The contractor shall provide evidence to the Employer as soon as practicable after

the respective insurance have been taken out but in any case prior to the start of work at the Site that insurance required under the Contract have been effected.

10.2 Compliance with Statutes and Regulations:

The Contractor shall conform in all respects, including by giving all notices and paying of all fees/charges, with the provision of:

(a) Any National or State Statute, Ordinance or other Law or any regulation or bye-law of any local or other duly constituted authority in relation to the execution and completion of the Works and the remedying of any defects therein, and

(b) The rules and regulations of all public bodies and companies whose property or rights are affected or may be affected in any way by the Works, and the Contractor shall keep the Employer indemnified against all penalties and liabilities of every kind for breach of any such provision.

(c) Any changes required for approval due to revision of the local laws.

(d) The Contractor shall abide by the provisions of the Minimum Wages Act, 1948 and Child Labour (Prohibition and Regulation) Act, 1986.

11. Default contractor in Compliance

In case of default on the part of Contractor in carrying out such instruction within the time specified therein or, if none, within a reasonable time, the Employer shall be entitled to employ and pay other persons to carry out the same and all costs consequent thereon or incidental thereto shall be determined by the Engineer and shall be recoverable from the Contractor by the Employer, and may be deducted by the Employer from any payments due or to become due, to the Contractor and the Engineer shall notify the Contractor accordingly.

12. Time for Completion

The time limit of work shall be as mentioned in the letter of commencement/Work Order and shall start from the date of issue of letter or as informed by through Letter/Work Order or as decided by Regional Director.

13. Extension of Time for Completion

The extension of the period for completion of work can only be granted on the valid and unavoidable grounds by the competent authority as per same terms and conditions of Contract and based on the requirements of Employer/Users.

14. Termination of Contract:

The employer reserves it's right to terminate the contract/works by giving 30 days notice at any time during currency of the contract, if the services of the contractor are not found satisfactory as per the opinion of employer or his representative for which no claim or compensation shall be entertained by the Employer.

15. Defect Identification and its rectifications

Contractor shall immediately attend the defects and complaints after getting intimation at site. Defect Liability period shall be 12 months from the date of completion of work under Bill of Quantities for measurable works. The contractor shall rectify at his own expenses, any defect in the work carried out by him during this period. On failure of the contractor to do so, the same shall be executed by the Employer through other means as deemed fit, at the risk and cost of the contractor.

16. Compensation for Delay

If the Contractor fails to complete the work in time then the Employer can impose liquidated damages on the contractor @ 1% per day maximum of 10 % of estimated cost.

17. Contractor's Failure to Carry out Instructions

In case of default on the part of the Contractor in carrying out defect rectification works, the Employer shall be entitled to employ and pay other persons/agency to carry out the same and if such work, in the opinion of the Employer, the Contractor was liable to do at his own cost under the Contract, then all costs consequent thereon or incidental thereto shall be determined and recovered from the Contractor by the Employer and may be deducted from any payment due or to become due to the Contractor.

18. Instruction for Variations

Quantities given in the Bill of Quantity may increase or decrease from the provision of contract quantity being estimated quantities. The quantity of any particular item may vary to any extent. Variation in quantity in particular items or overall cost, does not entitle contractor to claim for any extra rate then tendered.

19. Method of Measurement

The Engineer shall determine by measurement of the value of actual work done in accordance with the Contract and shall be paid proportionately. The works shall be measured net, notwithstanding any general or local custom, except where otherwise provided in the Contract. The method of measurements shall be followed as per the CPWD Norms / Specifications.

20 (A). Certificates and Payments

The contractor shall submit a bill in three copies by 7th day of every month for the work executed up to the date of previous month in the tabulated form. The bill must be supported with the following documents.

- a) Measurement of all the works executed.
- b) Abstract of the all parts of bill.
- c) Test Reports.
- d) Copy of certified attendance sheet of staff/workmen engaged with their copy of wages register, ESI, EPF Challan, Bank statement for salary compliance etc.

- e) A self-certificate by agency stating, 'They are adhering to all statutory laws including labour laws & minimum wages act.'
- f) Complaint registration form duly signed by complainant on satisfactory work completion

After receipt of the bills submitted by the contractor in the manner prescribed by the above duly supported by all the documents, the Engineer shall check the bills and certify the payments admissible to the contractor. The payment shall be released only after certification of the engineer for the works carried out at site.

20 (B). Timing of Payments: - Applicable when if submitted as per clause 20(A)

Amount which is due with respect to each interim payment shall be paid as follows: -

- i) 50% of the value of the ARM bills submitted along with all details and supporting documentation complete in all respects against the work executed and claimed in the submitted bills.
- ii) The balance amount due after checking of the bills by the Employer within 30 working days.

21.1 Deduction of Income tax

The amount to be deducted towards the income tax shall be at the rate applicable.

21.2 Labour Welfare Cess

Rate on the work done shall be deducted from each bill as per statutory requirements, as applicable.

22. Performance Guarantee:

Within **10** days of issue of letter of Work Order/Intent of Work/acceptance of tender, the Contractor shall submit a Performance Guarantee@ 5% of the Value of Contract amount for proper performance of the Contract in the form as specified in the contract. The Performance guarantee shall be initially valid for the duration of the contract period plus 365 days.

The performance security can be en-cashed by the Employer to recover any amount which is payable by the contractor to the Employer on any account for a cause arising out of the contract.

23. Correction of Certificates:

The Engineer may have issued any Interim Payment Certificate, the correction or modification in any previous Interim Payment Certificate which has been issued by him, and shall have authority, if any work is not being carried out to his satisfaction, to omit or to reduce the value of such work in any Interim Payment Certificate.

24. Final Certificates:

Within 90 days after receipt of the Final Statement, and the written discharge, the Engineer shall report to the employer (with a copy to the Contractor) with a Final Certificate stating:

- (a) The amount which, in the opinion of the Engineer, is finally due under the Contract, and

(b) After giving credit to the Employer for all amounts previously paid by the employer and for all sums to which the Employer is entitled under the contract.

25. Default of Contractor:

If the performance of the contract is not satisfactory and not corrected within 15 days of receiving notice, then employer shall be at liberty to terminate the contract and get the work executed through other means at the risk and cost of the Contractor.

26. Amicable Settlement of Dispute:

The parties (the Employer and the Contractor) shall use their best efforts to settle amicably all disputes arising out of or in connection with this contract or the interpretation thereof.

27. Arbitration:

Any dispute and differences relating to the meaning of the specifications, designs, drawings and instructions herein before mentioned and as to the quality of workmanship of materials used in the work or as to any other question, claim, right, matter or thing whatsoever in any way arising out of or relating to the contract, designs, drawings, specifications, estimates, instructions or these conditions or otherwise concerning the works or the execution of failure to execute the same whether arising during the progress of the work or after the completion or abandonment thereof in respect of which amicable settlement has not been reached shall be referred to the Sole Arbitrator appointed by the Chief Engineer, Employees' State Insurance Corporation, who shall proceed as per the Arbitration Act, 1996.

28.1. The Work under the contract shall continue, during the Arbitration proceedings.

28.2. The award of the Arbitrator shall be final, conclusive and binding on both the parties (the Employer and the Contractor).

29. Payment on Termination:

In the event of termination of the contract, employer shall be at liberty to get balance work done at the risk and cost of the contractor and due payment of the contractor, if any, shall be released after the completion of whole of the works.

Regional Director
Employees' State Insurance Corporation

Sign and seal of Contractor:

Date:

Place:

Particular Conditions of Contract

- CPWD specifications shall be followed. Where not available, BIS/Engineering practice as directed by the Engineer shall be followed. The materials shall be got approved prior to its use for work from the Engineer-In-Charge of the ESIC.
- Formats of Performance Guarantee and Contract Agreement are at Annexure I and Annexure H respectively.
- As the work will have to be carried out in building and area in use, the contractor shall ensure:
 - a. All design/drawing work/s involved in this tender is/are in the scope of Contractor, which is/are to be submitted by them to ESIC with the vetting/certification of Government Engineering College/NIT/ IIT before execution of respective and allied work/s.
 - b. That the normal functioning of Employees' State Insurance Corporation activity shall not be affected as far as possible.
 - c. That the work will be carried out in an orderly manner without noise and obstruction to flow of traffic.
 - d. That all rubbish etc. will be disposed off at the earliest and the place will left clean and orderly at the end of each day's work.
 - e. The work shall be carried out by the qualified worker for their part of work. He shall be responsible for their conduct. The staff shall behave in a courteous manner. The contractor shall be held responsible for any loss or damage to Employees' State Insurance Corporation property.
 - f. The contractor shall ensure safety of his workers and others at site of work and shall be responsible for any consequence arising out of execution of the Repair work.
 - g. When instructed to do so, the contractor shall ensure proper record keeping and storing of irreparable/dismantled material.
 - h. The contractor has to make his own arrangement for use of the same including extending temporary lines etc. The responsibility for following relevant rules, regulations and loss in the regard shall be entirely that of the contractor.
 - i. The contractor shall take proper care during dismantling operations to ensure that there is no danger/damage to any adjoining/existing structures and in case of any damage the contractor shall re-do the work/do the necessary repairs as per direction of the Engineer-in-Charge, for which no claim would be entertained by the department.
 - j. For any/s substituted items/deviations in quantities of BOQ items, Contractor has to intimate to ESIC and obtained prior approval from Competent Technical Authority before work execution.
 - k. The work shall be carried out in manner complying in all respects with the requirement of relevant byelaws of the local Municipal Corporation or the other local Govt. body whatsoever.
 - l. The contractor shall put necessary boards on display forbidding the residents/staff/ public from approaching the building under repair to avoid any accident.

- m. The contractor shall take all precautions to avoid all accidents by exhibiting necessary caution-boards. They shall be responsible for all damages and accidents caused due to negligence on their part.
- n. All incidental charges of any kind including cartage, storage, cutting, wastage and safe custody of materials etc. (not covered under any other condition) shall be borne exclusively by the contractor and nothing extra shall be payable to them on this account.
- o. All warning boards and displays, such as REPAIR WORK IN PROGRESS, KEEP AWAY FROM BUILDING, NO PARKING etc. along with sufficient supervisory staff on ground shall be provided by the contractor, wherever required. Nothing extra shall be payable on this account.
- p. Water and Electricity shall be arranged for his/her/their work at the site by the contractor at his own cost. Nothing extra shall be payable on this account.
- q. The site of work shall always be kept neat and clean due to constraints of working space in and around buildings. To avoid nuisance to the occupants/staff, all building rubbish unserviceable materials shall be periodically removed from the premises to the approved municipal grounds and all necessary permissions in this regard have to be obtained by the contractor from the Competent Authorities. Nothing extra shall be payable on this account.
- r. Since the work is to be carried out in the occupied buildings, proper sequencing as regards dismantling of sanitary pipes, GI pipes, toilets etc. shall be done so as to cause minimum inconvenience to the occupants besides taking care of the constraint of keeping the system functional during repairs by making temporary arrangements, as required. Nothing extra shall be payable on this account.
- s. The area of dismantling / guiniting / replastering / repairing as per relevant items etc. given in the tender may have to be got done in patches, at different heights / levels also for which nothing extra shall be payable.
- t. Lifting of materials such as cement, sand, wooden planks etc. through the building lifts is prohibited. No mixing or offloading etc. of mortar / cement concrete etc. over the open terrace / flooring shall be permitted. Arrangements as deemed it shall be made without making inconvenience to the occupants/staff/public, by the contractor for mixing/ lifting/offloading all materials etc. at no extra cost.
- u. The services of contractor may be utilized for Branch Offices/Dispensaries of SRO Aurangabad jurisdictions as and when required/directed by the Employer, on the same terms, conditions & rates as per this agreement.
- v. Minimum numbers of Technical Manpower as per CPWD norms shall be engaged by contractors to supervise the work.

Additional Terms and Conditions for Civil Works

GUARANTEE FOR WATER PROOFING TREATMENT

Five years guarantee in prescribed (attached) Performa attached must be given by the contractor for the water proofing treatment. In addition 10 (ten percent) of the cost of these items would be retained as guarantee to watch the performance of the work executed. However, half of this amount (withheld) would be released after two monsoon season after the completion of the work if the performance of the water proofing work done is found satisfactory. If any defect is noticed during the guarantee period it should be rectified by the contractor within seven days and, if not attended to, the same shall be got done by other contractor/agency at the risk and cost of the contractor. In any case the guaranteeing firms during the guarantee period should inspect and examine the treatment once in every year and make good any defect observed. However, the security deposit can be released in full, if a call receipt of a Bank Guarantee from scheduled Bank/Fixed Deposit receipt of Scheduled Bank/Demand Draft of scheduled Bank issued / drawn in favour of ESI FUND ACCOUNT No.1, payable at Mumbai for 5 (Five) year is produced and deposited with the department.

PRODUCT DELIVERY, STORAGE AND HANDLING :-

- a. The contractor shall construct storage space for chemicals and other materials to ensure that the storage conditions are as recommended by the manufactures.
- b. All the materials shall be procured and delivered in sealed containers with labels equable and intact.
- c. All the chemicals (polymers, rusti-cides, epoxy water proofing compound, etc.) shall be procured in convenient packs, say 20 litres (kgs.) capacity packing only or as approved by the Engineer-in-Charge, and not in bigger capacity containers, say 200 litre (Kgs.) drums.
- d. All required material for the ARM Work shall be got approved, procured and deposited with the departmental supervisory staff. The material will be kept in joint custody of the Contractor and the department. The watch and ward of such material shall however, remain to be the responsibility of the Contractor and no claim, whatsoever, on this account shall be entertained. Different containers of each chemical shall be serially numbered on packing and also consumed in that order. Day to day account of receipt, issue and balance will be regulated by the department and proper account shall be maintained at the site of work in the prescribed form as per standard practice.
- e. All the chemicals shall be procured by the contractor directly from the manufacturer or their authorized dealers and copies of challans / cash memos towards the quantity of various chemicals procured shall be made available by the contractor to the department and the same shall be kept in record. The name of manufacturers, manufacturer's product identification, manufacturer's mixing instructions, warning for handling and toxicity and date of manufacturing and shelf life shall be clearly and legibly mentioned on the labels of the each container.
- f. The contractor shall submit for the chemicals procured, manufacturer's and /or authorized dealer's certificate regarding supplying and verifying conformance to the material specification, as specified.
- g. All filled containers shall be handled in safe manner and in a way to avoid breaking container seals.
- h. Empty containers of the chemicals should not be removed from site till the completion of work and shall be removed only with the written approval of the Engineer-in-Charge.

- i. All arrangement for measuring, dosing and mixing of material / chemicals at site has to be made by the contractor. Nothing extra shall be payable on this account.
- j. Contractor shall suitably advise his site Engineer and all the workers as regard safe handling of chemicals. Necessary protective and safety equipments in form of hand gloves, goggles etc. shall be provided by the contractor at no extra cost and also used at site.
- k. All incidental charges of any kind including cartage, storage, wastage and safe custody of material etc. shall be borne by the contractor and no claim, whatsoever, shall entertained on this account.

LIST OF PREFERED MAKE

No.	Materials	Approved Brands
1.	Cement (Grey)	Ambuja, Birla, ACC, Ultra Tech., Binani , J. P. Rewa, Vikram, Shri Cement, Birla J & K & cement Corporation of India.
2.	Steel	SAIL/ TISCO/Jindal Steel/ RINL or other primary producer of steel as approved by Ministry of Steel .
3.	Floor Tiles (Mosaic) ISI marked	Shyam Tiles, Super Tiles, Hind Mosaic, Vyaara Tiles
4.	Floor Tiles (Chequered) (ISI marked only)	Shyam Tiles, Super Tiles, Hind Mosaic, Vyaara Tiles
5.	C.P. Brass Bib Cock, Pillar Cock, Stop Cock etc. (ISI marked only)	Jaguar, Marc, Hindware, Parryware
6.	C.P. Brass Shower Rose 125 mm dia	Jaguar, Marc, Kohler, Grohe.
7.	C.P. Brass Towel rail	Jaguar, Marc, Hindware, Parryware, kohler, grohe.
8.	C.P. Brass Flush Valve (ISI Marked)	Jaguar Marc ,Hindware, Parryware Kohler, Grohe.
9.	C.P. Brass Waste Coupling	Jaguar, Marc, Kohler, Grohe .
10	Urinal Stalls (ISI Marked only)	Hindware, Neycer, Parryware, Cera
11	Squatting Pan (ISI Marked only)	Hindware, Neycer, Parryware, Cera
12	P.V.C. Flush Tank (ISI Marked only)	Hindware, Neycer, Parryware, Cera
13	Wash Basin (ISI Marked only)	Hindware, Neycer, Parryware, Cera
14	Water Closets (ISI Marked only)	Hindware, Neycer, Parryware, Cera
15	Kitchen Sink (Fire Clay) (ISI Marked only) (IS771)	Sunfire, Padmani, R.K.C.P, Prayag, Jayna, Neelkanth
16	Kitchen Sink (Stainless Steel)(ISI Marked only)	Nirali, Blue Star, Prayag, Jayna, Neelkanth
17	G.I. Pipes (ISI Marked only)	Asian, Tata, Jindal
18	PVC Tanks (ISI Marked only)	Sintex, Electroplasto, Plastoor Equivalent

19	C.I. Pipes (ISI Marked only)(IS:1536)	Truform Engineers, Neco,Kapilansh
20	D.I. Pipes	Electro Steel Castings Limited, Kapilansh
21	Flush Door Shutters (ISI Marked only)	Kutty, Kenwood,Swastik, Duro, Kitply, Century.
22	Aluminium Door Fittings (ISI Marked only)	Classic, Prestige, Shalimar or Equivalent
23	Oxidised M.S. door Fittings (ISI Marked only)	Ashish or equivalent
24	Black Enamelled M.S. Hinges (ISI Marked only)	Ashish or equivalent
25	Steel Door / Window Frames	AGEW, SenHarvik , Shiv Mular, Steel Plast
26	Mortice Lock (ISI Marked only)	Godrej, Harrison, Dorset
27	Steel Sectional Windows/ Ventilators	AGEW, SenHarvik , Shiv Mular, Steel Plast
28	Particle Board/ Plywood (ISI Marked only)	Kitboard, Anchor, Archid, Duro, National
29	Aluminium Extruded Body Diecast Door Closures (ISI Marked only) (IS :3564)	Hardywyn, Everite , or Equivalent
30	Stone Ware Pipes Grade-A (ISI Marked only)	Sonya, Supertech, Cherry
31	Centrifugally Cast Soil Pipes (ISI Marked only)	NECO, BIC, Kapilansh or Equivalent
32	C.I. Rain Water pipes (ISI Marked only)	NECO, BIC, Kapilansh or Equivalent
33	UPVC Rain Water Pipes (ISI Marked only)(IS :13592)	Astron Fittings (14375), Finolex Supreme, Prince
34	Steel Tubes for structural purposes (ISI Marked only) (IS: 1161)	TATA , Jindal, Surya or equivalent
35	Manhole Covers (ISI Marked only)(IS:1726)	Neco,Kapilansh or equivalent
36	Water Proofing Compound (ISI Marked only)	Fosroc, Pidilite, Sapseal,STP
37	Ceramic Floor Tiles	Kajaria, Somany, Orient-BellJhonson
38	Ceramic Wall Tiles	Kajaria, Somany, Orient-Bell,Jhonson
39	Putty (ISI Marked only) (IS:419)	J K , Birla Shalimar or equivalent
40	Anodized Aluminium Section (ISI Marked only)	Jindal, Indalco, Hindalco
41	Factory made concrete blocks	Sabar, Ved PMC ,JK,Eco green

42	White cement (ISI Marked only)	Birla White, J.K. White or equivalent
43	Glass sheet (Float / Plain) (ISI Marked only)	Modi Float, Saint Gobin, Asahi
44	PTMT Ball Cock (ISI Marked only)	PrayagJaquar, Kohler,Grohe or Equivalent
45	PTMT Accessories (ISI Marked only)	Prayag , Jaquar, Kohler,Grohe or Equivalent
46	G.I. Fittings	R. Brand, DRP,Zolto,ICs,Unik
47	Clamps for pipes	Chilly or Equivalent
48	Gate Valves (ISI Marked)	Zoloto , Leader,Sant
49	CPVC Pipes	Astral, Supreme, Kissan
50	External Premium Acrylic Paint	Apex Ultima of Asian Paints, Dulux Weather Shield Max of ICI Dulux
51	External Smooth Acrylic Paint	Apex of Asian Paints, Weather Shield of ICI Dulux
52	Acrylic Plaster	NITCO, Asian Paints
53	Interlocking Paver Blocks	Super, Duracrete, NITCO,Vyyara
54	Vitrified floor tiles	Kajaria, Somany, Orient-Bell, RAK.
55	Oil Bound Washable Distemper / Acrylic distemper	Asian paint / Berger/ Dulux/Nerolac
56	Cement Primer	Asian paint / Berger/ Dulux /Nerolac
57	Red Oxide Zinc Chromate primer	Asian paint / Berger/ Dulux /Nerolac
58	Plastic Emulsion Paint	Asian paint / Berger/ Dulux /Nerolac
59	Synthetic Enamel Paint	Asian paint / Berger/ Dulux /Nerolac
60	Pigment	Asian paint / Berger/ Dulux/ Nerolac
61	Plaster of Paris	Birla, JK or equivalent
62	Epoxy Paint	Asian Paint, Berger, Dulux/ Nerolac
63	Plastic Seat with lid	Parryware, Hindware, Seabird, Orient (Coral)
64	PVC Shutters & Frame	Rajashree,Plastiwood
65	PVC Rigid Pipes	Duke, Supreme, Prince,
66	RMC Plant	L & T, RMC, ACC, Ultratech, Godrej.

67	APP Sheet for water proofing treatment	Asian paint, Shalimar S.T.P.
68	Acrylic Polymer	Anuvi Chemical, SunandaSpe. Coating Pvt. Ltd, SKG Constn. Chemical Pvt. Ltd
69	Rusticide	Anuvi Chemical, SunandaSpe. Coating Pvt. Ltd, SKG Constn. Chemical Pvt. Ltd
70	Passivator	Anuvi Chemical, SunandaSpe. Coating Pvt. Ltd, SKG Constn. Chemical Pvt. Ltd
71	Water Proofing Compound	Fosrock, CICO, Pidillite, BASF, Laticrete, Ardex, Endira.

TESTING OF MATERIALS

The contractor shall procure all the materials in advance so that there is sufficient time for testing and approving of the material and clearance of the same before use in the work.

The contractor's rates for the items involving the use of materials shall be deemed to cover the cost of samples, the cost of packaging, sealing, transportation, loading, unloading etc. shall be borne by the contractor, Testing charges shall be borne by the Department only when the samples satisfy the provisions specified & conform to the requirements of the relevant specifications. If the results show that the samples do not satisfy the relevant specifications, the testing charges shall be borne by the contractor.

In case of concrete and reinforced concrete work, the contractor shall be required to make arrangement for carrying out comprehensive strength tests at his own cost. He shall render all assistance for the preparation of cubes, safe custody of the same, proper curing and carriage up to the laboratory where the test is to be performed the cubes tests can be performed at any laboratory approved by the Engineer-In-Charge.

Testing of materials should be got done through the following Testing laboratories.

1. All Government Institutes having testing Laboratory facility.
2. Indian Institute of Technology, Powai, Navi Mumbai.
3. National Test House, Andheri, Mumbai.
4. National Institutes of Technology.
5. Central Government / State Government Research Centres.
6. Centrally or State Government funded Laboratories stands approved.
7. Laboratory as approved by the competent authority.
8. National Council for Cement and Building Materials, Ahmedabad, Gujarat.

Sign and Seal of Contractor:

Date:

Place:

Regional Director
Employees' State Insurance Corporation

CONTRACT AGREEMENT

This CONTRACT (hereinafter called the “Contract”) is made on the day of the month of _____ between Regional Director, Regional Office, Employees' State Insurance Corporation, Panchdeep Bhavan, 108, N.M Joshi Marg, Lower Parel, Mumbai – 400 013 on the one hand (hereinafter called the Employer) and on the other hand(hereinafter called the Contractor).

WHEREAS

The Employer has accepted the offer of the contractor to provide **“ANNUAL REPAIR & MAINTENANCE OF CIVIL WORKS OF DISPENSARY CUM BRANCH OFFICE INCLUDING STAFF QUARTERS AT WALUJ, AURANGABAD”**

AND WHEREAS The Contractor, having represented to the Employer that they have the required professional skills, personnel and technical resources, have agreed to provide the services and execute the works on the terms and conditions set forth in this Contract Agreement.

Now therefore the parties hereto/hereby agree as follows:

1.0 The following documents attached hereto shall be deemed to form an integral part of this contract:

1	Notice Inviting Tender	Annexure 'A'
2	Eligibility Criteria for Bidders	Annexure 'C'
3	Instruction to the bidders	Annexure 'D'
4	Scope of work	Annexure 'E'
5	General Conditions of Contract	Annexure 'F'
6	Particular Conditions of Contract	Annexure 'G'
7	Format of Contract Agreement	Annexure 'H'
8	Form of Performance Security Band Guarantee Bond	Annexure 'I'
9	Additional Terms & Conditions for Civil works	Annexure-'P'
10	Schedule of Work	Annexure-'Q'

2.0 The mutual rights and obligations of the Employer and the Contractor shall be as set forth in the contract in particular:

- a) The Contractor shall carry out the services in accordance with the provisions of the contract and,
- b) The Employer shall make payments to the contractor in accordance with the provisions of the contract.

In witness whereof, the parties hereto have caused this contract to be signed in their respective names as of the day and year first above written.

Signature and Seal of Contractor

Dated at _____
Corporation,

Regional Director,
Employees' State Insurance

Panchadeep Bhavan, N.M. Joshi Marg,
Lower Parel, Mumbai-400013

FORM OF PERFORMANCE SECURITY BANK GUARANTEE BOND

In consideration of the Employees' State Insurance Corporation having agreed under the terms and conditions of the Agreement no. dated made between Employees' State Insurance Corporation and Second Party (here in called the said Contractor for the work hereinafter called the said agreement) to production of irrevocable bank guarantee for Rs. (Rs. only) as a Security/Guarantee from the Construction Agency for compliance of his obligations in accordance with the terms and conditions in the said agreement.

1. We(hereinafter referred as to "The Bank" hereby) (indicate the name of the bank) Undertake to pay to the Employees' State Insurance Corporation an amount not exceeding Rs.(Rs. only IN WORDS) on demand by the Employees' State Insurance Corporation.

2. We do hereby undertake to pay the amounts due and payable under this Guarantee without any demure, merely on a demand from the Employees' State Insurance Corporation stating that the amount claimed is required to meet the recoveries due or likely to be due from the Second Party. Any such demand made on the Bank shall be conclusive as regards the amount due and the payable by the bank under this Guarantee. However, our liability under this guarantee shall be restricted to an amount not exceeding Rs.(Rs. only IN WORDS)

3. We, the said bank further undertake to pay to the Employees' State Insurance Corporation any money that is demanded notwithstanding any dispute or disputes raised by the Second Party in any suit or proceeding pending before any court or Tribunal relating thereto, a liability under this present being absolute and unequivocal.

The payment so made by us under this bond shall be a valid discharge of a liability for payment there under and the Second Party shall have no claim against us making such payment.

4. We further agree that the guarantee herein contained shall remain in full force and effect during the period that would taken for the performance of the said agreement and that it shall continue to enforceable till all the dues of the Employees' State Insurance Corporation under or by virtue of the said agreement have been fully paid and its claims satisfied or discharged or Engineer-in-charge on behalf of the Employees' State Insurance Corporation certified that the terms and conditions of the said agreement have been fully and properly carried out by the said Second Party and accordingly discharges this guarantee.

5. We(indicate the name of Bank) further agree with the Employees' State Insurance Corporation that, the Employees' State Insurance Corporation shall have the fullest liberty without our consent and without effecting in any manner our obligations hereunder to vary any of the terms and conditions of the said agreement or to extend time of performance by the said contractor(s) from time to time or to postpone for any time or from time to time any of the powers exercisable by the Employees' State Insurance Corporation against the said Second Party and to bear or enforce any of the terms and conditions relating to the said agreement and

we shall not be relieved from our liability by reason of any such variation, or extension being granted to the said contractor or for any forbearance, act of omission on the part of the Employees' State Insurance Corporation or any indulgence by the Employees' State Insurance Corporation to the said contracts or by any such matter or thing whatsoever which under the law relating to sureties would, but for this provision, have effect of so relieving us.

6. This guarantee will not be discharged due to the change in the constitution of the Bank of the contractor,

7. Welastly undertake not to revoke this guarantee except with the previous consent of the Employees' State Insurance Corporation in writing.

8. This guarantee shall be valid up to Unless extended on demand by Employees' State Insurance Corporation. Notwithstanding anytime mentioned above, our liability against this guarantee is restricted to Rs.(Rs. only) and unless a claim in writing is lodged with us within six months of the date of expiry of the extended date of expiry of this guarantee all our liabilities under this guarantee shall stand discharged.

Dated Day of

For(indicate the name of Bank)

TECHNICAL BID PERFORMA**1. GENERAL INFORMATION**

NAME OF THE AGENCY/ FIRM ALONG WITH ADDRESS AND TELEPHONE / MOBILE NO AND E-MAIL ADDRESS.	
NAME OF OWNER/ ALL PARTNERS/ ALL DIRECTORS	
TYPE OF FIRM (Proprietorship/ Partnership / Pvt. Ltd/Ltd.)	
BANK ACCOUNT NUMBER WITH BANK NAME AND ADDRESS	

2. STATUTORY AND OTHER REQUIREMENTS:

Particulars	<u>Registration Number</u>	<u>Copy Enclosed</u> (Yes/No)
Certificate of Incorporation/ Registration of Firm		
Registration details as Civil Contractor with C.P.W.D.s/ State P.W.D.s./M.E.S./ Railways/ BSNL Civil wing or any other government body (along with year of registration)		
Valid copy of ESI Registration		
Valid copy of EPF Registration		
GST Registration upto date file return.		
PAN No. under Income Tax		
Professional Tax Registration		
Labour (Central) Registration Certificate or Undertaking.		

3. DETAILS OF COMPLETED WORK AS PER SL. NO. 3 OF ANNEXURE - C :

Name of Government Body	Details of the Completed Works of Similar Nature	Cost of the Completed Works	Copy of Certificate issued by Govt. Body Enclosed (Yes/No)

4. DETAILS OF BALANCE SHEET/ P&L ACCOUNT DURING LAST THREE FINANCIAL YEAR :

Financial Year	Copy Enclosed (Yes/No)	Income (Rs.)	Expenditure (Rs.)	Net Profit/ Loss (Rs.)
2015-2016				
2016-2017				
2017-2018				

5. COPIES OF INCOME TAX RETURN DURING LAST THREE FINANCIAL YEAR :

Financial Year	Income Tax Return Enclosed (Yes/No)
2015-2016	
2016-2017	
2017-2018	

Sign and Seal of Contractor:

Date:

Place:

EXPERIENCE OF COMPANY

Experience of similar nature of completed work as per eligibility conditions.

1	Project title & Location :	
2	Name of the Client and Address :	
3	Describe area of participation (Specific Work done/services rendered by the applicant)	
4	Period of work Done/Services rendered for the project	
5	Total cost of similar nature of work as per completion Certificate	
6	Date of start of the work	
7	Date of completion of the work	
8	Completion Certificate issued by	
7	Any other details, if any	

NOTE :-

Supporting authenticated documents, like completion certificates from the client in support of each of the above works/project to be furnished in original when asked for.

Sign and Seal of Contractor :

Date :

Place:

UNDERTAKING

1. I/we, the undersigned certify that I have gone through the terms and conditions mentioned in the tender document and undertake to comply with them.
2. The rates quoted by me are valid and binding upon me for the entire period of contract.
3. The earnest money of Rs. _____ to be deposited by me has been enclosed herewith vide demand Draft/ Banker Cheque no. _____ dated: _____ drawn on Bank _____ Branch _____.
4. I hereby undertake to provide the services as per directions given in the tender documents / order within stipulated period.
5. I/We give the rights to Regional Director, ESIC to forfeit the earnest money deposited by me/us if any delay occur on my/agent's part of failed to provide the services within the scheduled time or service of desired quality.
6. This is to declare and certify that neither myself nor my firm has ever been blacklisted by any Govt./Semi Govt./Public/Private Institution.
7. I/We hereby certify that the firm posses all the required license/ certification to perform the work.

Sign and Seal of Contractor: _____

Full Name: _____

Designation: _____

Date : _____

Place: _____.

**CONSENT LETTER FROM ELIGIBLE ASSOCIATE AGENCY OF MINOR
COMPONENT OF WORK**

Name of work: - _____.

1. I / We hereby give my consent to associate with M/s, for executing the minor component of work of (Mention category).
2. I / We will execute the work as per specifications and conditions of the agreement and as per directions of the Engineer –in-Charge for the corresponding minor work till the completion of the work.
3. I / We will be responsible for necessary action to handover the installations and for rectification of defects and repair during the maintenance / warranty period.
4. Also I / We will employ full time technically qualified Engineer / supervisor for the minor component of the work as required for the work. I / We will attend inspection of officers of the department as and when required.

Date:

Signature with date of Major component

Signature with date of Associate/ Minor Component

Contractor
Address

Contractor
Address

1. Witness with address
(From major component contractor side)

2. Witness with address
(From minor component contractor side)

MEMORANDUM OF UNDERSTANDING (M.O.U)
(to be submitted for each and every MINOR component)

1. M/s. (Name of the firm with full address)
Enlistment Status
Valid Upto:
(Henceforth called the main Contractor)
2. M/s. (Name of the firm with full address)
Enlistment Status
Valid Upto:
(Henceforth called Associated Contractor)

For the execution of Minor Work:

(Minor Component) as per schedule specifications, terms and conditions of the tender.

We state that M.O.U between us will be treated as an agreement and has legality as per Indian Contract Act (amended upto date) and the department (CPWD) can enforce all the terms and conditions of the agreement for execution of the above work. Both of us shall be responsible for the execution of work as per the agreement to the extent this MOU allows.

Both the parties shall be paid consequent to the execution as per agreement to the extent this MOU permits. In case of any dispute, either of us will go for mediation by the Engineer In-charge. Any of us may appeal against the mediation to the Regional Director, Regional Office, Mumbai. His decision shall be final and binding on both of us.

We have agreed as under:

1. The Associated Contractor will execute all Minor works in the wholesome manner as per terms and conditions of the agreement.
2. The Associated Contractor shall be liable for disciplinary action if he fails to discharge the action(s) and other legal action as per agreement.
3. All the machinery and equipments, tools and tackles required for execution of the Minor works, as per agreement, shall be the responsibility of the Associated Contractor.
4. The site staff required for the Minor work shall be arranged by the Associated Contractor as per terms and conditions of the agreement.
5. Site order book maintained for the said work shall be signed by the main contractor as well as by the Engineer of the Associated Contractor and by Associated Contractor himself.
6. All the correspondence regarding execution of the Minor work shall be done by the department with the Associated Contractor with a copy to the main contractor. In case of non-compliance of the provisions of agreement, the main contractor, as well as the associated

contractor shall be responsible. The action under clauses 2 and 3 shall be initiated and taken against the main contractor.

SIGNATURE OF MAIN CONTRACTOR

SIGNATURE OF ASSOCIATED
CONTRACTOR

Date:
Place:

Date
Place:

ANNEXURE- O

**GUARANTEE BOND TO BE EXECUTED BY THE CONTRACTOR
FOR REMOVAL OF DEFECTS AFTER COMPLETION IN RESPECT OF
WATER-PROOFING WORKS (All Water - Proofing Items).**

The agreement made this..... day of (Two Thousand _____ only)
..... betweenS/o(hereinafter called the
GUARANTOR of the one part) and the Regional Director_____ (hereinafter called
the Government of the other part)

WHEREAS THIS agreement is supplementary to a contract (Hereinafter called the Contract) dated
..... and made between the GUARANTOR OF THE ONE PARTAND the Government of the
other part whereby the contractor inter alia undertook to render the building and structures in the said
contract recited completely water and leak-proof.

AND WHEREAS THE GUARANTOR agreed to give a guarantee to the effect that the said
structures will remain water/leak proof for (5) five years from the date of completion of work.

NOW THE GUARANTOR hereby guarantees that work executed by him will render the structures
completely leak proof and the minimum life of such water proofing treatment shall be (5) five years to be
reckoned from the date after the expiry of maintenance period prescribed in the contract.

The decision of the Engineer-in-charge with regard to nature and cause of defect shall be final and
binding on Guarantor.

During this period of guarantee, the guarantor shall make good all defects and in case of any defect
being found render the building water proof to the satisfaction of the Engineer-In-Charge calling upon him
to rectify the defects failing which the work shall be got done by the Department by some other contractor
at the Guarantor's cost and risk. The decision of the Engineer-in-charge as to the cost payable by the
Guarantor shall be final and binding.

That if the guarantor fails to execute the water proofing or commits breach there under, then the
guarantor will indemnify the principal and his successor against all loss, damage, cost expense or otherwise
which may be incurred by him by reason of any default on the part of the GUARANTOR in performance
and observance of this supplementary agreement. As to the amount of loss and/or damage and / or cost
incurred by the Government, the decision of the Engineer-in-charge will be final and binding on both the
parties.

IN WITNESS WHEREOF these presents have been executed by the obligator.....and
..... by for and on behalf of the Regional
Director,_____ on the day, month and year first above written.

SIGNED, sealed and delivered by OBLIGATOR in the presence of :-

1. 2.

SIGNED FOR AND BEHALF OF THE REGIONAL DIRECTOR BYin
the presence of :-

..... in the presence of :-

1. 2.

Schedule of Work:

BILL OF QUANTITIES						
ANNUAL REPAIR & MAINTENANCE OF CIVIL WORKS OF DISPENSARY CUM BRANCH OFFICE INCLUDING STAFF QUARTERS AT WALUJ, AURANGABAD						
A. CIVIL WORK SCHEDULE						
SN	DSR No.	Description of Item	Qty	Units	Rate	Amount
		DSR ITEMS				
	1.1	Carriage of materials By Mechanical Transport including loading, unloading and stacking (Lead 15 Km)				
1	1.1.1	Lime, Murrum, Building rubbish	8.00	Cum	229.51	1,836.05
2	1.1.2	earth	8.00	Cum	286.88	2,295.01
	2.8	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.			-	-
3	2.8.1	All kinds of soil	2.00	Cum	192.51	385.02
	2.10	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m :			-	-
	2.10.1	All kinds of soil			-	-
4	2.10.1.2	Pipes cables tec. Exceeding 80mm dia but not exceeding 300mm dia	30.00	Mtr	260.82	7,824.69
5	2.34	Supplying chemical emulsion in sealed containers including delivery as specified. 2.34.1 Chlorpyriphos/ Lindane emulsifiable concentrate of 20%	5.00	litre	215.13	1,075.63

6	2.35.3	Treatment of soil under existing floors using chemical emulsion@ one litre per hole, 300 mm apart including drilling 12 mm diameter holes and plugging with cement mortar 1 :2 (1 cement: 2 Coarse sand) to match the existing floor: 2.35.3.1 With Chlorpyriphos/Lindane E.C. 20% with 1% concentration	150.00	sqm	152.60	22,889.27
7	4.17	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement: 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth.	60.00	Sqm	521.01	31,260.59
8	8.3	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge. 8.3.2 Granite work	100.00	metre	284.25	28,425.03
9	8.12	Providing and laying flamed finish Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge : 8.12.1 Flamed finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.	200.00	Sqm	3,340.95	6,68,190.73
10	8.9	Stone tile (polished) work for wall lining over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand) and cement slurry @ 3.3 kg/sqm including fixing of granite slab with ss clamps screws the rate in inclusive of cost for clamps & screws, pointing in white cement complete. 8.9.1 8 mm thick 8.9.1.2 Granite of any colour and shade	50.00	sqm	2,334.62	1,16,731.21

11	9.1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). 9.1.2 Sal wood	1.25	cum	98,784.16	1,23,480.20
	9.7	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick:			-	-
	9.7.7	Float glass panes			-	-
12	9.7.7.2	5.5 mm thick glass panes	20.00	sqm	1,685.37	33,707.44
	9.20	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters.			-	-
13	9.20.2	30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	25.00	Sqm	2,745.09	68,627.31
	9.46	Providing and fixing curtain rods of 1.25 mm thick chromium plated brass plate, with two chromium plated brass brackets fixed with C.P. brass screws and wooden plugs, etc., wherever necessary complete:			-	-
14	9.46.2	20 mm dia	20.00	Mtr	415.67	8,313.48
	9.48	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete.			-	-
15	9.48.2	Fixed to openings/ wooden frames with rawl plugs screws etc	50.00	Kgs	130.09	6,504.67
16	9.83	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete	5.00	Each	479.48	2,397.39

	9.95	Providing and fixing ISI marked aluminium butt hinges anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :			-	-
17	9.95.1	125x75x4 mm	50.00	Each	136.75	6,837.28
18	9.95.4	100x63x4 mm	50.00	Each	91.92	4,595.79
19	9.95.6	75x63x4 mm	50.00	Each	71.79	3,589.28
	9.96	Providing and fixing aluminium sliding door bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete:			-	-
20	9.96.1	300x16 mm	10.00	Each	245.78	2,457.83
21	9.96.2	250x16 mm	10.00	Each	218.89	2,188.85
	9.97	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with necessary screws etc. complete:			-	-
22	9.97.2	250x10 mm	20.00	Each	101.92	2,038.46
23	9.97.4	150x10 mm	20.00	Each	74.39	1,487.77
24	9.97.5	100x10 mm	20.00	Each	56.92	1,138.39
	9.100	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete:			-	-
25	9.100.2	100 mm	60.00	Each	52.18	3,130.57
26	9.100.3	75 mm	40.00	Each	45.06	1,802.45
	9.101	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete.			-	-
27	9.101.1	Single rubber stopper	25.00	Each	31.87	796.81
28	9.101.2	Twin rubber stopper	25.00	Each	43.96	1,099.06
29	9.113	Providing and fixing bright finished 100 mm mortice lock with 6 levers without pair of handles of approved quality for aluminium door, with necessary screws etc complete as per direction of Engineer-in-charge.	5.00	Each	547.97	2,739.83

	9.117	Providing and fixing factory made uPVC door frame made of uPVC extruded sections having an overall dimension as below (tolerance ± 1 mm), with wall thickness 2.0 mm (± 0.2 mm), corners of the door frame to be Jointed with galvanized brackets and stainless steel screws, joints mitred and plastic welded. The hinge side vertical of the frames reinforced by galvanized M.S. tube of size 19 X 19 mm and 1 mm (± 0.1 mm) wall thickness and 3 nos. stainless steel hinges fixed to the frame complete as per manufacturer's specification and direction of Engineer-in-charge			-	-
30	9.117 .2	Extruded section profile size 42x50 mm	30.00	RM	237.40	7,121.88
	9.120	Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture . M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30 mm thickness, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5 mm thick, 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10 mm (5 mm x 2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail. panelling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame welded/ sealed to the styles & rails with 7 mm (5 mm+2 mm) thick x 15 mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge, manufacturer's specification & drawing.			-	-
31	9.120 .1	30 mm thick plain PVC door shutters	10.00	Sqm	3,202.41	32,024.15
32	10.3	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer.	11.00	sqm	6,201.74	68,219.10

	10.25	Steel work welded in built up sections / framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.			-	-
33	10.25 .2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	50.00	Kgs	99.44	4,971.78
	11.20	Chequered precast cement concrete tiles 22mm thick in footpath & out yard jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing and cleaning etc. complete on 20mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand)			-	-
34	11.20 .3	Dark shade using ordinary cement	25.00	Sqm	828.75	20,718.63
35	11.36	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	100.00	Sqm	861.66	86,165.91
36	11.37	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigment etc., complete	5.00	Sqm	796.35	3,981.76
	11.41	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete.			-	-
37	11.41 .2	Size of Tile 600x600 mm	20.00	Sqm	1,295.03	25,900.68
	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion,(i) Single socketed pipes.			-	-
38	12.41 .1	75 mm diameter	50.00	Mtr	172.09	8,604.44

39	12.41 .2	110 mm diameter	50.00	Mtr	273.43	13,671.67
	12.42	Providing and fixing on wall face unplasticised-PVC moulded fittings / accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion.			-	-
40	12.42 .1.2	Coupler 110 mm dia	10.00	Each	118.76	1,187.56
41	12.42 .3.2	Single tee with door - 110x110x110 mm	10.00	Each	210.04	2,100.35
42	12.42 .5.2	Bend 87.5° - 110 mm bend	10.00	Each	130.85	1,308.45
43	12.42 .6.2	Shoe (Plain) 110 mm Shoe	12.00	Each	113.38	1,360.51
	12.43	Providing and fixing unplasticised-PVC pipe clips of approved design to unplasticised-PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length, including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 coarse sand) and making good the wall etc. complete.			-	-
44	12.43 .1	75 mm	20.00	Each	211.19	4,223.84
45	12.43 .2	110 mm	20.00	Each	209.86	4,197.23
	13.4	12 mm cement plaster of mix :			-	-
46	13.4. 1	1:4 (1 cement: 4 coarse sand)	25.00	Sqm	209.23	5,230.63
	13.5	15 mm cement plaster :			-	-
47	13.5. 1	1:4 (1 cement : 4 coarse sand)	50.00	Sqm	242.54	12,127.20
48	13.11	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand).	200.00	Sqm	295.65	59,129.16
49	13.21	Extra for providing and mixing water proofing material in cement plaster work in proportion recommended by the manufacturers	10.00	Per bag 50 kg cement used in the mix	58.25	582.50
50	13.26	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	75.00	Sqm	137.32	10,299.30
	14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per directions of Engineer-In-Charge.			-	-

51	14.1. 1	With cement mortar 1:4 (1 cement : 4 fine sand)	100.00	Sqm	306.35	30,634.71
	14.6	Renewing glass panes, with wooden fillets wherever necessary:			-	-
52	14.6. 1	Float glass panes of thickness 4 mm	10.00	Sqm	986.37	9,863.73
53	14.6. 2	Float glass panes of thickness 5.5 mm sqm	50.00	Sqm	1,287.92	64,395.95
54	14.9	Renewal of old putty of glass panes (length)	100.00	metre	29.44	2,944.31
	14.42	White washing with lime to give an even shade :			-	-
55	14.42 .1	old work (two or more coats)	300.00	Sqm	11.86	3,557.47
	14.45	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade:			-	-
56	14.45 .1	Old work (one or more coats)	300.00	Sqm	38.59	11,578.26
57	14.46	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	400.00	Sqm	12.49	4,997.81
	14.53	Wall painting with plastic emulsion paint of approved brand and manufacturer to gve an even shade.			-	-
58	14.53 .1	Two or more coats on new work	100.00	Sqm	63.92	6,391.87
	14.54	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :			-	-
59	14.54 .1	One or more coats on old work	1000.0 0	Sqm	59.35	59,348.97
60	14.75 A	Cleaning of terrace/loft water storage tank (inside surface area) upto 2000 litre capacity at all heights with coconut brushes, duster etc., removal of silt, rubbish from the tank and cleaning the tank with fresh water disinfecting with bleaching powder @ 0.5gm per litre capacity of tank, including marking the date of cleaning on the side of tank body with the help of stencil and paint and disposing of malba, all complete as per direction of Engineer-in-Charge. (The old date already written on tank should be removed with paint remover or black paint and if date is not written with the stencil or old date is not removed deduction will be made @ Rs. 0.10 per litre if during cleaning any GI fittings or ball cock is damaged that is to be repaired by contractor at his own cost and nothing extra will be paid on this account)	5000.0 0	litre	0.23	1,156.90

61	14.76	Cleaning and desilting of gully trap chamber, including removal of rubbish mixed with earth etc. and disposal of same, all as per the direction of Engineer-in-charge.	10.00	Each	55.01	550.11
62	14.77	Cleaning of choked sewer line by diesel running vehicle mounting hydraulic operated high pressure suction cum jetting sewer cleaning machine fitted with pump having 4000 litres suction capacity and 6000 litres water jetting tank capacity including skilled operator, supervising engineer etc. for cleaning and partial desilting of manholes and Dec hocking of sewer lines. Dec hocking and flushing of sewer line from one manhole to another by high pressure jetting system of 2200 PSI for sewer line from 150mm dia upto 300mm dia for all depth.	50.00	Mtr	251.97	12,598.64
	14.78	Cleaning of under ground sump, Over Head R.C.C. Tank (independent staging) including disposal of slit and rubbish, all as per direction of Engineer-in-Charge. The cleaning shall consist following operations:-			-	-
63		(i) Tank shall be emptied of water by pumping & bottom shall be cleaned of slit and other deposits.(ii) Entire surface area of the sump shall then scrubbed thoroughly with wire brush etc. and pressure washed with water.(iii) Chlorination of RCC internal surface by liquid chlorine.(iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface.(v) Finally the surface shall be treated with ultraviolet radiation etc. as per direction of Engineer-in-Charge.	1000.00	Sqm	47.09	47,085.83
64	14.81	Cutting holes of required size in brick masonry wall for fixing of exhaust fan including providing and fixing 300 mm dia PVC pipe conforming BIS-12818 and making good the same etc. complete as per direction of Engineer-in-charge.	15.00	Each	160.11	2,401.72
65	14.84	Dismantling 15 to 40 mm dia G.I. pipe including stacking of dismantled pipes within 50 metres lead as per direction of Engineer- in-Charge. (a) Internal Work - Exposed on wall	50.00	mtr	2.31	115.69
66	14.85	Taking out existing wooden door shutter, repair by cutting,painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws,etc. as required, all complete as per the direction of the Engineer-in-charge.	25.00	Each	204.08	5,101.93
	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.			-	-

67	15.2.1	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	3.00	Cum	1,153.49	3,460.46
68	15.3	Demolishing R.C.C. work manually / by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge.	2.00	Cum	1,682.77	3,365.54
	15.7	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.			-	-
69	15.7.4	In cement mortar	2.00	Cum	974.98	1,949.95
	15.13	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead :			-	-
70	15.13.1	Of area 3 sq. metres and below	15.00	Each	70.86	1,062.90
	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.			-	-
71	15.23.2	For thickness of tiles above 25 mm and up to 40 mm	200.00	Sqm	56.92	11,383.90
72	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	200.00	Sqm	25.91	5,182.91
73	15.57	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	50.00	sqm	28.11	1,405.63
74	16.83	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	100.00	sqm	62.41	6,241.48
75	16.84	Laying old cement concrete interlocking paver blocks of any design/shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineering-charge. (Old CC paver blocks shall be supplied by the department free of cost).	100.00	sqm	242.02	24,202.35

	17.1	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:			-	-
76	17.1.1	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	5.00	Each	4,042.44	20,212.20
	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :			-	-
77	17.2.1	W.C. pan with ISI marked white solid plastic seat and lid	5.00	Each	3,955.09	19,775.47
	17.7	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:			-	-
78	17.7.1	White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C. P. brass pillar taps	5.00	Each	2,659.19	13,295.96
	17.18	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete.			-	-
79	17.18.1	10 litre capacity - White	10.00	Each	961.96	9,619.62
	17.10	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS 13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required:			-	-
	17.10.1	Kitchen sink with drain board			-	-
80	17.10.1.4	510x1040 mm bowl depth 178 mm	2.00	Each	4,297.02	8,594.03
81	17.16 A	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge.	10.00	Each	294.78	2,947.78

		Providing and fixing solid plastic seat with lid for pedestal type W.C.pan complete :			-	-
	17.20					
82	17.20 .1	White solid plastic seat with lid each	5.00	Each	474.56	2,372.80
		Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.			-	-
	17.28					
	17.28 .2	Flexible pipe			-	-
83	17.28 .2.1	Flexible pipe - 32 mm dia	30.00	Each	84.74	2,542.29
		Providing and fixing 600x450 mm bevelled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.				
84	17		5.00	Each	946.29	4,731.43
		Providing and fixing soil, waste and vent pipes :				
	17.35				-	-
	17.35 .1	100 mm dia			-	-
85	17.35 .1.1	Sand cast iron S&S pipe as per IS: 1729	20.00	metre	998.17	19,963.47
	17.35 .2	75 mm diameter :			-	-
86	17.35 .2.1	Sand cast iron S&S pipe as per IS: 1729	20.00	metre	823.94	16,478.88
		Providing and fixing bend of required degree with access door, insertion rubber washer 3 mm thick, bolts and nuts complete.				
	17.38				-	-
	17.38 .1	100 mm dia			-	-
87	17.38 .1.1	Sand cast iron S&S as per IS - 1729	12.00	each	394.21	4,730.56
	17.38 .2	75 mm dia			-	-
88	17.38 .2.1	Sand cast iron S&S as per IS - 1729	12.00	each	313.98	3,767.79
		Providing and fixing plain bend of required degree.				
	17.39				-	-
	17.39 .1	100 mm dia			-	-
89	17.39 .1.1	Sand cast iron S&S as per IS - 1729	8.00	each	501.77	4,014.17
	17.39 .2	75 mm dia			-	-
90	17.39 .2.1	Sand cast iron S&S as per IS -1729	8.00	each	253.53	2,028.28
		Providing and fixing single equal plain junction of required degree with access door, insertion rubber washer 3 mm thick, bolts and nuts complete.				
	17.43				-	-

	17.43 .1	100x100x100 mm			-	-
91	17.43 .1.1	Sand cast iron S&S as per IS - 1729	5.00	each	560.87	2,804.33
	17.43 .2	75x75x75 mm			-	-
92	17.43 .2.1	Sand cast iron S&S as per IS - 1729	5.00	each	418.80	2,093.99
	17.60	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors :			-	-
	17.60 .1	100 mm inlet and 100 mm outlet			-	-
93	17.60 .1.2	Sand Cast Iron S&S as per IS: 1729	6.00	Each	905.16	5,430.95
	17.60 .2	100 mm inlet and 75 mm outlet			-	-
94	17.60 .2.2	Sand Cast Iron S&S as per IS- 1729	6.00	Each	905.16	5,430.95
	17.70	Providing and fixing PTMT Bottle Trap for Wash basin and sink.			-	-
95	17.70 .2	Bottle trap 38 mm single piece moulded with height of 270 mm, effective length of tail pipe 260 mm from the centre of the waste coupling, 77 mm breadth with 25 mm minimum water seal, weighing not less than 263 gms	5.00	Each	353.49	1,767.45
96	17.78	Providing and fixing white vitreous china extended wall mounting water closet of size 780x370x690 mm of approved shape including providing & fixing white vitreous china cistern with dual flush fitting, of flushing capacity 3 litre/ 6 litre (adjustable to 4 litre/ 8 litres),including seat cover, and cistern fittings, nuts, bolts and gasket etc complete.	3.00	each	11,205.39	33,616.16
	18.7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.			-	-
97	18.7. 1	15mm nominal outer dia pipes	10.00	Mtr	165.38	1,653.79
98	18.7. 2	20 mm nominal outer dia Pipes	10.00	Mtr	208.18	2,081.84
99	18.7. 3	25 mm nominal outer dia pipes	10.00	Mtr	250.12	2,501.22
100	18.7. 4	32 mm nominal outer dia Pipes	10.00	Mtr	334.40	3,344.02
101	18.7. 5	40 mm nominal outer dia Pipes	10.00	Mtr	445.98	4,459.85
102	18.7. 6	50 mm nominal outer dia Pipes	10.00	Mtr	634.62	6,346.17

	18.8	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work , including cutting chases and making good the walls etc.				-	-
103	18.8.2	20 mm nominal outer dia pipes	10.00	Mtr	329.54	3,295.43	
	18.10	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, I/c cutting and making good the walls etc. Internal work - Exposed on wall				-	-
104	18.10.1	15 mm dia nominal bore	15.00	Mtr	215.65	3,234.69	
105	18.10.2	20 mm dia nominal bore	15.00	Mtr	259.72	3,895.86	
106	18.10.3	25 mm dia nominal bore	15.00	Mtr	286.74	4,301.06	
107	18.10.4	32 mm dia nominal bore	15.00	Mtr	356.73	5,350.95	
108	18.10.5	40 mm dia nominal bore	5.00	Mtr	456.40	2,281.99	
109	18.10.6	50 mm dia nominal bore	5.00	Mtr	546.52	2,732.60	
	18.11	Providing and fixing G.I. Pipes complete with G.I. fittings and clamps,i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall :				-	-
110	18.11.1	15 mm dia nominal bore	15.00	metre	330.53	4,957.89	
	18.12	Providing and fixing G.I. pipes complete with G.I. fittings and clamps,i/c cutting and making good the walls etc. Internal work - Exposed on wall				-	-
111	18.12.3	25 mm dia nominal bore	25.00	Mtr	238.15	5,953.70	
112	18.12.6	50 mm dia nominal bore	12.00	Mtr	396.47	4,757.64	
	18.18	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete:				-	-
113	18.18.3	25 mm nominal bore	2.00	Each	383.99	767.97	

	18.47	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws, including excavation, refilling the earth or cutting of wall and making good the same complete wherever required :			-	-
114	18.47 .3	25 mm nominal bore	15.00	Each	490.87	7,363.09
115	18.47 .6	50 mm nominal bore	5.00	Each	789.99	3,949.95
116	18.48	Providing and placing on terrace (at all floor levels) Polyethylene water storage tanks ISI 12701 marked with cover and suitable locking arrangements and making necessary holes for inlet outlet and over low pipes but without fittings and the base support of the tank	5000.0 0	Per Litre	8.39	41,937.63
	18.51	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms.			-	-
117	18.51 .1	15 mm nominal bore	10.00	each	569.83	5,698.31
	18.52	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931.			-	-
118	18.52 .1	15 mm nominal bore	10.00	each	631.61	6,316.10
	18.53	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931			-	-
119	18.53 .1	15mm nominal bore	10.00	each	550.34	5,503.37
	19.1	Providing, laying and jointing glazed stoneware pipes class SP-1 with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete :			-	-
120	19.1. 1	100 mm diameter	15.00	Mtr	250.18	3,752.69
121	19.1. 4	250 mm diameter	20.00	Mtr	801.15	16,023.07
	19.2	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete as per standard design :			-	-
122	19.2. 1	100 mm diameter S.W. pipe	15.00	Mtr	720.69	10,810.36
123	19.2. 4	250 mm diameter S.W.Pipes	20.00	Mtr	1,188.14	23,762.73

124	19.4	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design: 19.4.3 180x150 mm size P type 19.4.3.1 With common burnt clay F.P.S. (non modular)bricks of class designation 7.5	5.00	each	1,974.31	9,871.54
	19.5	Dismantling of old S.W. pipes including breaking of joints and bed concrete stacking of useful materials near the site within 50 m lead and disposal of unserviceable materials into municipal dumps :			-	-
125	19.5.1	100 mm diameter	15.00	Mtr	42.05	630.80
126	19.5.4	250 mm diameter	20.00	Mtr	52.41	1,048.15
	19.7	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4coarse sand) with R.C.C. top slab with 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design			-	-
	19.7.2	Inside size 120x90 cm and 90 cm deep including C.I. cover with frame (medium duty) 500 mm internal diameter, total weight of cover and frame to be not less than 116 kg (weight of cover 58 kg and weight of frame 58 kg) :			-	-
127	19.7.2.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	2.00	Each	21,312.87	42,625.75
	19.8	Extra for depth for manholes			-	-
	19.8.1	Size 120x90 cm			-	-
128	19.8.2.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	1.00	RM	7,925.57	7,925.57

	21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, panelling and dash fasteners to be paid for separately) :				-	-
	21.1.1	For fixed portion				-	-
129	21.1.1.2	Powder coated aluminium (minimum thickness of powder coating 50 micron)	50.00	Kgs	444.83	22,241.40	
	21.1.2	For shutters of doors, windows & ventilators including providing and fixing hinges / pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately).				-	-
130	21.1.2.2	Powder coated aluminium (minimum thickness of powder coating 50 micron)	50.00	Kgs	514.70	25,735.24	
	21.2	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer-in-Charge.				-	-
131	21.2.1	Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side	10.00	Sqm	956.00	9,560.04	
	21.3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):				-	-
132	21.3.2	With float glass panes of 5.50 mm thickness	10.00	Sqm	1,161.47	11,614.70	

	21.4	Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125 kg, for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge.			-	-
133	21.4.1	With stainless steel cover plate minimum 1.25 mm thickness	4.00	Each	2,376.74	9,506.94
	21.8	Filling the gap in between aluminium frame & adjacent RCC/ Brick/Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete.			-	-
134	21.8.1	Upto 5mm depth and 5 mm width	2000.00	meter	72.25	1,44,496.81
135	21.18	Providing and fixing 12 mm thick frameless toughened glass door shutter of approved brand and manufacture, including providing and fixing top & bottom pivot & spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-in-charge (Door handle, lock and stopper etc.to be paid separately).	4.00	sqm	5,331.98	21,327.91
136	22.5	Providing and laying water proofing treatment in sunken portion of WCs, bathroom etc., by applying cement slurry mixed with water proofing cement compound consisting of applying : (a) First layer of slurry of cement @ 0.488 kg/sqm mixed with water proofing cement compound @ 0.253 kg/ sqm. This layer will be allowed to air cure for 4 hours. (b) Second layer of slurry of cement @ 0.242 kg/sqm mixed with water proofing cement compound @ 0.126 kg/sqm. This layer will be allowed to air cure for 4 hours followed with water curing for 48 hours. The rate includes preparation of surface, treatment and sealing of all joints, corners, junctions of pipes and masonry with polymer mixed slurry.	100.00	Sqm	345.10	34,510.33

	22.20	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer 3 mm thick water proofing membrane, black finished reinforced with non-woven polyester matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the same membrane manufacture of density at 25°C, 0.87-0.89 kg/litre and viscosity 70-160 cps. Over the primer coat the layer of membrane shall be laid using Butane Torch and sealing all joints etc, and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 650/450N/5cm. Tear strength in longitudinal and transverse direction as 300/250N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM,D - 5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane :				
137	22.20 .1	3 mm thick	170.00	sqm	482.54	82,032.31
138	21.13	Providing and fixing 100mm brass locks (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete.	5.00	each	415.33	2,076.64
139	24.2	Providing and fixing double scaffolding system (cup lock type) on the exterior side of building/structure, upto 25 metre height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40mm dia M.S. tube, placed 1.5 metre centre to centre, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes, M.S. tube chalis, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and/ or pointing and/ or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connecting with the building etc, wherever required, if feasible, for inspection of work at required locations with essential safety features for the workmen etc., complete as per directions and approval of Engineer-in-charge. Note:- (1) The elevational area of the scaffolding shall be measured for payment purpose.(2) The payment will be made once only for execution of all items for such works.	1000.0 0	sqm	185.22	1,85,219.69

	<p>Designing, fabricating, testing, installing and fixing in position Curtain Wall with Aluminium Composite Panel Cladding, with open grooves for linear as well as curvilinear portions of the building ,for all heights and all levels etc. including:</p> <p>(a) Structural analysis & design and preparation of shop drawings for pressure equalisation or rain screen principle as required, proper drainage of water to make it watertight including checking of all the structural and functional design.</p> <p>(b) Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc.</p>				
140	<p>(c) The fastening brackets of Aluminium alloy 6005 T5 / MS with Hot Dip Galvanised with serrations and serrated washers to arrest the wind load movement, fasteners, SS 316 Pins and anchor bolts of approved make in SS 316, Nylon separators to prevent bi-metallic contacts all complete required to perform as per specification and drawing The item includes cost of all material & labour component, the cost of all mock ups at site, cost of all samples of the individual components for testing in an approved laboratory, field tests on the assembled working curtain wall with aluminium composite panel cladding, cleaning and protection of the curtain wall with aluminium composite panel cladding till the handing over of the building for occupation. Base frame work for ACP cladding is payable under the relevant aluminium items The Contractor shall provide curtain wall with aluminium composite panel cladding, having all the performance characteristics all complete , as per the Architectural drawings, as per item description, as specified, as per the approved shop drawings and as directed by the Engineer-in-Charge. However, for the purpose of payment, only the actual area on the external face of the curtain wall with Aluminium Composite Panel Cladding (including width of groove) shall be measured in sqm. up to two decimal places."</p>	50.00	sqm	3,940.29	1,97,014.29

	26.22	Providing and fixing false ceiling at all heights with integral densified calcium silicate reinforced with fibre and natural filler false ceiling tiles of Size 595x595 mm of approved texture, design and patterns having NRC (Noise Reduction coefficient) of 0.50 (minimum) as per IS 8225:1987, Light reflectance of 85% (minimum). Non combustible as per BS:476 (part-4), fire performance as per BS:476 (part 6 &7),humidity resistance of 100%, thermal conductivity < 0.043 W/m K as per ASTM 518:1991,in true horizontal level suspended on interlocking metal T-Grid of hot dipped galvanised iron section of 0.33mm thick (galvanized @ 120 grams per sqm including both sides) comprising of main-T runners of size 24x38 mm of length 3000 mm, cross - T of size 24x32 mm of length 1200 mm and secondary intermediate cross-T of size 24x32 mm of length 600mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 50 mm long, 8 mm outer diameter M-6 dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 85x25x25x2 mm. Galvanised iron perimeter wall angle of size 24x24x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450 mm centre to centre and 40 mm long dry wall S.S screws. The work shall be carried out as per specifications, drawing and as per directions of Engineer-in-Charge.				
141	26.22 .1	With 15 mm thick regular edged light weight calcium silicate false ceiling tiles.	75.00	sqm	1,774.05	1,33,053.62
142	26.30	Drilling suitable holes in reinforced or plain cement concrete with power driven drill machine to a minimum depth of 100mm upto 200mm in RCC beams, lintels, columns and slabs to introduce steel bars for sunshades/balconies including fixing the steel bars in position using epoxy resin anchor grout of approved make but excluding the cost of reinforcement, all complete as per direction of Engineer-In-Charge. 26.30.1 Upto and including 12mm dia.	2.00	each	82.31	164.63
	26.35	Providing and injecting approved grout in proportion recommended by the manufacturer into cracks/honey-comb area of concrete/masonry by suitable gun/pump at required pressure including cutting of nipples after curing etc. complete as per directions of Engineering-Charge. (The payment shall be made on the basis of actual weight of approved grout injected.)			-	-
143	26.35 .2	Stirrer mixed SBR Polymer (of approved make) modified Cement slurry made with Shrinkage Compensating Cement in concrete/RCC work.	25.00	kg	84.45	2,111.34

144	26.35 .3	Epoxy injection grout in concrete/RCC work of approved make	10.00	kg	745.56	7,455.64
145	26.39	Providing and inserting 12mm dia galvanised steel injection nipple in honey comb area and along crack line including drilling of holes of required diameter (20mm to 30mm) up to depth from 30mm to 80mm at required spacing and making the hole & crack dust free by blowing compressed air, sealing the distance between injection nipple with adhesive chemical of approved make and allow it to cure complete as per direction of Engineer-In-Charge.	25.00	each	170.64	4,266.07
		SUPPLY OF MATERIALS			-	-
	18.17	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :			-	-
146	18.17 .1A	20 mm nominal bore	10.00	Each	458.77	4,587.69
147	18.17 .1	25mm nominal bore	10.00	Each	495.38	4,953.85
148	18.17 .2	32mm nominal bore	3.00	Each	579.26	1,737.78
149	18.17 .3	40mm nominal bore	5.00	Each	676.44	3,382.20
150	18.17 .4	50mm nominal bore	5.00	Each	867.56	4,337.80
151	18.17 .5	65mm nominal bore	5.00	Each	1,488.70	7,443.49
		MARKET ITEMS			-	-
152		Supplying and fixing of GI Tee			-	-
153	MR	15mm dia	10.00	Each	27.30	273.00
154	MR	20mm dia	10.00	Each	33.05	330.50
155	MR	25mm dia	10.00	Each	77.15	771.50
156	MR	32mm dia	5.00	Each	93.45	467.25
157	MR	40mm dia	5.00	Each	104.45	522.25
158	MR	50mm dia	5.00	Each	132.50	662.50
		Supplying and fixing GI Bend				-
159	MR	15mm	10.00	Each	13.10	131.00
160	MR	20mm	10.00	Each	22.05	220.50
161	MR	25mm	10.00	Each	49.35	493.50
162	MR	32mm	5.00	Each	66.15	330.75
163	MR	40mm dia	5.00	Each	82.40	412.00
164	MR	50mm dia	5.00	Each	95.00	475.00

165		Supplying and fixing GI elbow				-
166	MR	15mm dia	10.00	Each	15.20	152.00
167	MR	20mm dia	10.00	Each	24.15	241.50
168	MR	25mm dia	10.00	Each	55.10	551.00
169	MR	32mm dia	5.00	Each	93.45	467.25
170	MR	40mm dia	5.00	Each	93.45	467.25
171	MR	50mm dia	5.00	Each	121.25	606.25
		Supplying and fixing reducer				-
172	MR	50x40mm dia	10.00	Each	88.20	882.00
173	MR	40x32mm dia	10.00	Each	66.15	661.50
174	MR	32x25mm dia	10.00	Each	49.35	493.50
175	MR	25x20mm dia	5.00	Each	27.30	136.50
		Supplying and fixing of hex nipple				-
176	MR	50 mm dia	5.00	Each	82.40	412.00
177	MR	40 mm dia	5.00	Each	66.15	330.75
178	MR	32 mm dia	8.00	Each	55.10	440.80
179	MR	25 mm dia	10.00	Each	41.45	414.50
180	MR	20 mm dia	15.00	Each	33.05	495.75
181	MR	15 mm dia	30.00	Each	22.05	661.50
182	MR	Jaquar make bib cock (DLX-511)	3.00	Each	600.00	1,800.00
183	MR	angular cock (jaquar LYR-38053)	3.00	Each	1000.00	3,000.00
184	MR	Bottle Trap (ALD-769L300x190	3.00	Each	1300.00	3,900.00
185	MR	Cleaning of septic tanks, with mechanically operated vacuum based septic tank cleaner including disposal of sludge far away from the campus by mechanical transportation using covered tanks without disturbing the public life etc. complete as per the direction of the Engineer-in-charge.	50.00	Cum	1000.00	50,000.00
186	MR	Cleaning the storm water drain around the office campus by using necessary tools and plants as directed etc. complete.	100.00	Mtr	40.00	4,000.00
	MR	Providing and erecting Structural sound and stable scaffolding of approved design on the external periphery of the building at all level and for all heights, it s removal, disposal of the unserviceable materials as per local by Laws, etc. complete as directed by Engr- in Charge				-

187		In wooden Ballies /Bamboos - Single Scaffolding with	200.00	Sqm	35.00	7,000.00
188	MR	Cleaning Inspection Chamber of size 0.9 x 1.2 depth not more than 1.2 mtrs and disposal of sludge in a excavated pit filled with earth on top lead not exceeding 50 mtrs	5.00	Each	500.00	2,500.00
189	MR	Providing and Fixing Vertical Fabric Blinds fixed at all levels and sizes as per the manufacturers specifications (MacDecor/Equivalent)	10.00	Sqm.	1000.00	10,000.00
190	MR	PVC pipe and fitting for plumbing work : Supply and fixing PVC Nanhi trap of size 100 X 75 mm in repair	10.00	No.s	132.05	1,320.50
191	MR	Supply and fixing PVC 75 mm dia bend in repair with plug in repair.	8.00	No.s	81.70	653.60
192	MR	Supply and fixing PVC 110 mm dia bend in repair with plug in repair.	6.00	No.s	142.90	857.40
193	MR	Supply and fixing PVC 75 mm dia "T" with plug in repair.	8.00	No.s	84.60	676.80
194	MR	Supply and fixing 110 mm dia PVC "T" in repair.	5.00	No.s	165.20	826.00
195	MR	Supply and fixing 75 mm dia PVC pipe in repair.(Type-A ISI)	20.00	R.M.	158.00	3,160.00
196	MR	Supply and fixing 110 mm dia PVC pipe in repair.(Type-A ISI)	20.00	R.M.	210.00	4,200.00
197	MR Ref. SOR-17-18	removing soil pan urinal wash basin and sink of any type ,size, make and brand including its bedding drainage fitting etc. complete	20.00	each	110.00	2,200.00
198	MR Ref. SOR-17-18	Providing & Applying Plaster of Paris punning to walls, beams, ceiling, columns in perfect line and level over the base of single quote cement plaster including roughing of existing surface making 6mm groove at skirting and door, widow jam, seal, lintel etc. complete. The rate is exclusive of base coat cement plaster.	50.00	sqm	298.00	14,900.00
199	MR Ref. SOR-17-18	Providing and Fixing 20mm +/- 2mm thick both side mirror polished approved colour granite urinal partition of 600 mm wide and 1550 mm high with round edges moulding and fixing in C.M.1:2 and filling joint in white cement mixed with pigment to match the colour of granite including quarrying, cleaning etc. complete	3.00	Nos	5344.00	16,032.00
200	MR Ref. SOR-17-18	Providing leak proof treatment by injection grouting method to old floor without removing tile of bath, with cement sand proportion of 1:1.5 and waterproofing compound at 2 kg/bag of cement mixed in 35 liters of water including drilling holes in required position grouting with above mixed solution and ceiling etc. complete.	20.00	litre	23.00	460.00
		Cradite for salvage value of following:				-
201		Iron/Steel	200.00	Kg	(30.00)	(6,000.00)

202		Plastic	100.00	Kg	(5.00)	(500.00)
203		Aluminium	100.00	kg	(50.00)	(5,000.00)
204		Brass	100.00	kg	(100.00)	(10,000.00)
205		Copper	20.00	kg	(330.00)	(6,600.00)
206		Wood	1.00	lump-sum	(2,200.00)	(2,200.00)
		Total Amount			(X)	33,15,826.70
	as per Central labour wage	Labour charges for maintaining day to day maintenance works at Offices, Dispensaries and residential quarters and attending to repairs with the maintenance staff with all helpers, tools and plants as directed the Engineer-in-charge as below :				
207		Plumber/Mason/Carpenter 26day x1	12.00	Months		2,21,376.00
208		Sewerman/Helper 26day x1	12.00	Months		1,67,196.00
		Total Amount			(Y)	3,88,572.00
		Total (X+Y)				37,04,398.70
		SAY				37,04,399